

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Macomb (County)

Located In: Shelby Twp.

Corner Code #7

RECORDED IN MACOMB COUNTY RECORDS AT: 8:30 A.M.

DEC 28 1993

Clerk - Recorder of Deeds MACOMB COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

- 1. Public Land Survey T 3 N R 12 E L-5
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

- 4. Lot No. , Recorded Plat
5. Private Claims

I, Huston K. Kennedy, in a field survey on December, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Set Post; 10" Ash S10°E 29 Lnks; 12" Elm N22°E 39 Lnks
1972-Avendt, P.S. #16034; Survey L.2352, Pg.6 - Fnd a Spike
1972-Avendt, P.S. #16034; LCRC L.2352, Pg.10 - Same wits as 1972 survey
1973-Cantrell, P.S. #5782; Survey L.2358, Pg.926 - Fnd a Spike
1973-Cantrell, P.S. #5782; LCRC L.2358, Pg.938-939 - Same wits as 1973 survey
1974-Kobs, P.S. #14097; LCRC L.2499, Pg.414 - Fnd PK Nail
1990-Avey, P.S. #30076; LCRC L.4983, Pg.762 - Set a Railroad Spike
1992-Avey, P.S. #15396; Survey L.5700, Pg.471 - Same wits as 1990 survey

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd a Railroad Spike in the centerline of 24 Mile Road, which is bituminous surface. There are tree lines extending to the North and South.

One witness point from the 1990 LCRC was found and it was used to recover and verify the location of the found Railroad Spike.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-20-93. FRANK J. DeDECKER, PS, PE, CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-5 I replaced the found Railroad Spike with 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623" in a monument box.
N55°E-62.01'-Set PK & Remon. tag in NW face Power Pole
N46°W-64.91'-Set PK & Remon. tag in SW face 18" Poplar
S60°W-85.15'-Set PK & Remon. tag SE face 12" Elm
S10°W-37.97'-Set PK & Remon. tag West face Power Pole

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by [Signature]

Date 12-14-93

Surveyor's Michigan License No. 17623

Grid table with columns A-M and rows 2-13. A dot is present at row 5, column L.