

LIBER 06166P046

B999659

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Macomb (County) Located In: Shelby Twp. Corner Code # L-7

1. Public Land Survey T 3 N R 12 E _____
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

RECORDED IN MACOMB COUNTY RECORDS AT: 8:30 A.M.

DEC 28 1993

L. M. ...
CLERK - REGISTER OF DEEDS
MACOMB COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

I, Huston K. Kennedy, in a field survey on December 14, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

- A. Description of original monument and accessories and/or subsequent restoration:
 1817-GLO Wampler, D.S.; Set Post; 17" Black Oak S83°E 13 Lnks; 18" White Oak S38°E 23 Lnks
 1975-Avey, P.S. #15396; LCRC L.2560, Pg.310 - Fnd 3/4" Square Bar
 1975-Avey, P.S. #15396; LCRC L.2601, Pg.208 - Same wits as 1975 LCRC
 1976-Kobs, P.S. #14097; LCRC L.2701, Pg.386 - Fnd 3/4" Square Bar
 1979-Landwehr, P.S. #10065; LCRC L.3102, Pg.146 - Same wits as 1975 LCRC
 1984-Kobs, P.S. #14097; LCRC L.3579, Pg.145 - Fnd 3/4" Square Iron Bar
 1986-Avey, P.S. #30076; LCRC L.4080, Pg.885 - Fnd 1/2" Iron Bar
 1989-Stephens, P.S. #29252; LCRC L.4576, Pg.494 - Fnd 3/4" Square Bar
 1990-Avey, P.S. #15396; LCRC L.4983, Pg.765 - Fnd 3/4" Square Bar

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 1993 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 3/4" Square Bar in the centerline of 23 Mile Road, which is bituminous surface. There are tree lines extending to the North and South.

The witness points from the 1990 LCRC were found and they were used to recover and verify the found 3/4" Square Bar.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-20-93.

Frank J. DeDecker
FRANK J. DeDECKER, PS, PE, CHAIRMAN

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 L-7 I replaced the found 3/4" Square Bar with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument M I Act 345 #17623" in a monument box.
 S70°E-120.42'-Set PK & Remon. tag SW face Power Pole
 S46°E-116.35'-Set PK & Remon. tag NE face Power Pole
 S00°-65.73'-Set PK & Remon. tag NE face 24" Maple
 N37°E-64.61'-Set PK & Remon. tag NW face 17" Maple

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by *[Signature]*
Surveyor's Michigan License No. 17623

Date 12/14/93

