

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Table with columns: Macomb (County), Located In: Shelby Twp., Corner Code #. Rows include Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec.

RECORDED IN MACOMB COUNTY
RECORDS AT: 8:30 A.M.

DEC 28 1993

Signature of Loretta A. ...
CLERK - REGISTER OF DEEDS
MACOMB COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

- 4. Lot No. ... Recorded Plat ...
5. Private Claims ...

Grid table with columns A-M and rows 2-13. A dot is present in cell J9.

I, Warren C. Avey in a field survey on November 30, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
GLO Corner - Set Post in 1817 - No Witnesses

LCRC 1985 Iron Bar L. 3829, P. 256
127.70' SW to pk nail in N face utility pole
90.92' Sly. to pk nail in N'wly. face 14" poplar
158.60' W.NW to c/l top nut f-hyd.
60.04' S to 1/2" bar #15396
1.40' E to W edge of wd. bridge

LCRC 1988 Iron in Mon. Box L. 4549, P. 99
127.80' SW to pk nail & tag in S side of p. pole
85.70' SE to pk nail N. side p. pole
91.02' S. to pk nail W side 20" Poplar
158.65' NW to c/l top hyd.

LCRC 1991 1/2" Bar in Mon. Box L. 5290, P. 288
158.58' W.NW to c/l top f-hyd.
60.09' S to 1/2" pipe
127.70' W.SW to pk nail N side p. pole
42.59' NE to pk nail in top of guard rail post

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" Bar in Mon. Box.

This corner location is supported by existing survey pts. in:
Victoria Sub. #1 L. 89, P. 14-16

Checked Witnesses

- 158.58' W.NW to c/l top f-hyd.
60.09' S. to 1/2" pipe
127.70' W.SW to pk nail N side p. pole
42.59' NE to pk nail in top of guard rail post

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-10-93. Signature of Frank J. DeDecker, PS, PE, CHAIRMAN.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced 1/2" B. with 3/4" Bar w/Alum. Cap Stamped "Macomb County Monument - MI Act 345" 30076

- 34.52' S to pk nail in MCW tag W face U. pole
85.90' SE to pk nail in MCW tag in NE face U. pole
18.44' N to pk nail in MCW tag on top guard rail post
127.83' SE to pk nail in MCW tag in NW face U. pole

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Warren C. Avey 30076

Date 12-6-93

Surveyor's Michigan License No. 30076

