

LIBER 051660083

B999696

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED IN MACOMB COUNTY RECORDS AT: 8:30 A.M.

For corners in

MACOMB (County)

Located In: SHELBY TOWNSHIP Corner Code #

DEC 28 1993

Clerk - Register of Deeds MACOMB COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

- 1. Public Land Survey T-3-N, R-12-E M-5
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

- 4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. Cell (2,6) contains '6', (2,7) contains '5', (2,8) contains '4', (2,9) contains '3', (2,10) contains '2', (2,11) contains '1'.

I, DAVID PAWLACZYK, in a field survey on NOVEMBER 23, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management; or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

POST WAS SET PER GOVERNMENT LAND OFFICE RECORDS N. 82° E, 7 LINKS 18" BLACK ASH S, 63° W, 8 LINKS 4" ASH

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" RE-ROD IN ASPHALT PAVEMENT LIBER 2352, PAGE 10 LIBER 2358, PAGE 938 LIBER 2832, PAGE 306 LIBER 3021, PAGE 208 LIBER 4479, PAGE 90 PREVIOUS LAND CORNER RECORDATION CERTIFICATES

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED 1/2" RE-ROD WITH P. A. 345 ALUMINUM CAP STAMPED # 17632 ON 3/4" x 24" IRON ROD. ACCESSORIES ESTABLISHED N. 80° W. 68.61 WITNESS TAG ON NORTH FACE UTILITY POLE N. 30° E. 42.98 WITNESS TAG ON WEST FACE UTILITY POLE S. 30° W. 61.79 WITNESS TAG ON WEST FACE UTILITY POLE DUE SOUTH 98.11 MONUMENT BOX A-5 NORTHWEST CORNER

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-15-93 FRANK J. DeDECKER, P.S., PE, CHAIRMAN

Signed by [Signature] Surveyor's Michigan License No. 17632

Date 12-24-93

