

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970 RECORDED IN MACOMB COUNTY

For corners in

MACOMB (County)

Located In: SHELBY TOWNSHIP Corner Code #

RECORDS AT: 8:30 A.M.

DEC 28 1993

Carmella Fournier CLERK - REGISTER OF DEEDS MACOMB COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

- 1. Public Land Survey T-3-N R-12-E M-6
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. Cell (6,13) contains a dot.

I, DAVID PAWLACZYK in a field survey on NOVEMBER 24, 1993 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A POST WAS SET PER GOVERNMENT LAND OFFICE RECORDS N. 52° E. 15 LINKS

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-15-93

FRANK J. DeDECKER, PS, PE, CHAIRMAN

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND A 3/4" PIPE IN GRAVEL ROAD (HAYES) PREVIOUS LAND CORNER RECORDATION CERTIFICATES LIBER 2358 PAGES 938-939 LIBER 3126 PAGE 161

AN UNRECORDED WITNESS SHEET FROM THE MACOMB COUNTY ROAD COMMISSION (UNDATED)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED THE 3/4" PIPE WITH P.A. #345 ALUMINUM CAP STAMPED #17632 ON 3/4" X 24" IRON ROD

ACCESSORIES ESTABLISHED

- S. 70° E. 114.33' NORTHWEST CORNER OF BRICK HOUSE
S. 10° E. 128.58' WITNESS TAG IN UTILITY POLE
N. 70° W. 35.77' E TOP OF HYDRANT
N. 30° W. 98.77' WITNESS TAG IN 12" POP

Signed by [Signature]

Date 12-20-93

Surveyor's Michigan License No. 17632

