

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MACOMB (County)

Located In: SHELBY TOWNSHIP Corner Code #

RECORDED IN MACOMB COUNTY RECORDS AT: 8:30 A.M.

DEC 29 1993

Clerk - Register of Deeds MACOMB COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

- 1. Public Land Survey T-3-N, R-12-E M-7
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

- 4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13 for recording purposes.

I, DAVID PAWLACZYK, in a field survey on NOVEMBER 24, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

POST WAS SET PER GOVERNMENT LAND OFFICE RECORDS S. 83° E. 6 LINKS 22" BLACK ASH N. 20° W. 17 LINKS 14" WHITE OAK

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" RE-ROD IN MONUMENT BOX IN ASPHALT ROAD PREVIOUS LAND CORNER RECORDATION CERTIFICATES LIBER 3062, PAGE 512 LIBER 3217, PAGE 914 LIBER 4080, PAGE 885

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-15-93 FRANK J. DeDECKER, PS, PE, CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED 1/2" RE-ROD WITH P.A. 345 ALUMINUM CAP STAMPED #17632 ON 3/4" x 24" IRON ROD. ACCESSORIES ESTABLISHED N. 50° W. 88.97 @ NUT TOP OF FIRE HYDRANT N. 45° E. 55.17 @ NUT TOP OF FIRE HYDRANT DUE EAST 36.82 WITNESS TAG ON SOUTH FACE UTILITY POLE S. 30° W. 48.52 WITNESS TAG ON SOUTHEAST FACE TRAFFIC POLE DUE SOUTH 152.79 NORTHWEST CORNER SECTION 19

Signed by [Signature] Date 12-24-93 Surveyor's Michigan License No. 17632