

LIBER **05166PG086**

**R999693**

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
MACOMB  
 (County)

Located In: 3 MELOBY Corner Code #  
TOWNSHIP

RECORDED IN MACOMB COUNTY  
 RECORDS AT: 8:30 A.M.

- |                                    |                            |             |
|------------------------------------|----------------------------|-------------|
| 1. Public Land Survey              | T <u>2-N</u> R <u>12-E</u> | <u>17-8</u> |
|                                    | T _____ R _____            | _____       |
|                                    | T _____ R _____            | _____       |
|                                    | T _____ R _____            | _____       |
| 2. Property Controlling in Section | S _____ T _____ R _____    | _____       |
|                                    | S _____ T _____ R _____    | _____       |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____    | _____       |
|                                    | S _____ T _____ R _____    | _____       |

**DEC 28 1993**

*Frank J. DeDecker*  
 CLERK - REGISTER OF DEEDS  
 MACOMB COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

|    | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2  | 6  | 5  | 4  | 3  | 2  |    |   |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |   |

I, David Pawlaczek in a field survey on November 29, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

PER THE GOVERNMENT LAND OFFICE RECORDS THE CORNER IS A 24" ELM. NO WITNESSES ARE GIVEN.

**ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-15-93**

*Frank J. DeDecker*  
**FRANK J. DeDECKER, PS, PE, CHAIRMAN**

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND A 1/2" RE-ROD IN A MONUMENT BOX PREVIOUS LAND CORNER RECORDATION CERTIFICATES  
LIBER 2898 PAGE 524  
LIBER 3062 PAGE 512  
LIBER 3217 PAGE 914  
LIBER 4060 PAGE 885  
LIBER 4576 PAGE 493  
AN UNDATED WITNESS SHEET FROM THE MACOMB COUNTY ROAD COMMISSION.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED THE 1/2" RE-ROD WITH P.A. #345 ALUMINUM CAP STAMPED W/ #17632 ON 3/4" X 24" IRON ROD  
ACCESSORIES ESTABLISHED  
N. 40° E. 55.55' WITNESS TAG IN 10" ELM  
S. 45° E. 50.10' WITNESS TAG IN 24" MAPLE  
S 45° W. 119.53' NORTHEAST CORNER BRICK GARAGE  
WEST 23.68' WITNESS TAG IN UTILITY PIPE  
N. 30° W. 91.56' & TOP OF HYDRANT

Signed by *David Pawlaczek* Date 12-24-93  
 Surveyor's Michigan License No. 17632

