

erroneous T designation  
LIBER 08166PG086

B999699

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MACOMB  
(County)

Located In: SHELDON Corner Code #  
TOWNSHIP

RECORDED IN MACOMB COUNTY  
RECORDS AT: 8:30 AM

DEC 28 1993

*Carmella Sabaugh*  
CLERK - REGISTER OF DEEDS  
MACOMB COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

C0211992 LIBER:06663 PAGE:849 11:17A 06/06/1995  
CARMELLA SABAUGH-MACOMB COUNTY, MI REG/DEEDS

- 1. Public Land Survey \* T ~~2~~14 N R 12-E M-8  
T 3 N R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

\* Being rerecorded to correct T2N, R12E to T3N, R12E

I, DAVID PAWLACZYK in a field survey on NOVEMBER 29, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

PER THE GOVERNMENT LAND OFFICE RECORDS  
THE CORNER IS A 24" ELM.  
NO WITNESSES ARE GIVEN.

ACCEPTED BY THE MACOMB COUNTY  
SURVEY PEER GROUP AS THE OFFICIAL  
CORNER UNDER MICHIGAN PUBLIC ACT 345  
OF 1990 AT A MEETING HELD ON  
12-15-93

*Frank J. Decker*  
FRANK J. DeDECKER, PS, PE, CHAIRMAN

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND A 1/2" RE-ROD IN A MONUMENT BOX  
PREVIOUS LAND CORNER RECORDATION CERTIFICATES  
LIBER 2898 PAGE 524  
LIBER 3062 PAGE 512  
LIBER 3217 PAGE 914  
LIBER 4060 PAGE 885  
LIBER 4576 PAGE 493  
AN UNDATED WITNESS SHEET FROM THE MACOMB  
COUNTY ROAD COMMISSION.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED THE 1/2" RE-ROD WITH P.A. #345 ALUMINUM  
CAP STAMPED W/ #17632 ON 3/4" X 24" IRON ROD  
ACCESSORIES ESTABLISHED

N. 40° E.	55.55'	WITNESS TAG IN 10" ELM
S. 45° E.	50.10'	WITNESS TAG IN 24" MAPLE
S. 45° W.	119.53	NORTHEAST CORNER BRICK GARAGE
WEST	23.68	WITNESS TAG IN UTIL. PIPE
N. 30° W.	71.56	& TOP OF HYDRANT

Signed by *David Pawlaczyk*  
Surveyor's Michigan License No. 17632

Date 12-24-93