

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MACOMB  
(County)

Located In: SHELBY Corner Code #  
TOWNSHIP

RECORDED IN MACOMB COUNTY  
RECORDS AT: 8130A

DEC 28 1993

*Carroll J. DeDecker*  
CLERK - REGISTER OF DEEDS  
MACOMB COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

- 1. Public Land Survey T-3-N R-12-E M-9  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, DAVID PAWLACZYK, in a field survey on DECEMBER 14, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

NO POST WAS SET PER GOVERNMENT LAND OFFICE RECORDS  
CORNER MARKED BY 6" BLACK ASH  
NO WITNESSES

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND IRON IN MONUMENT BOX  
LIBER 2208, PAGE 299  
LIBER 2898, PAGE 524  
LIBER 3217, PAGE 914  
LIBER 4576, PAGE 493  
LIBER 4549, PAGE 99  
PREVIOUS LAND CORNER RECORDATION CERTIFICATES

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED 1" IRON WITH P. A. 345 ALUMINUM  
CAP STAMPED # 17632 ON 3/4" x 24" IRON ROD.  
ACCESSORIES ESTABLISHED  
N. 50° E. 39.35 WITNESS TAG ON NORTH FACE UTILITY POLE  
N. 85° E. 73.03 & NUT TOP OF FIRE HYDRANT  
S. 50° E. 133.52 WITNESS TAG ON WEST FACE UTILITY POLE  
S. 36° W. 198.26 NORTHEAST CORNER OF BUILDING  
N. 78° W. 102.60 WITNESS TAG ON NORTH FACE UTILITY POLE  
N. 54° W. 57.64 WITNESS TAG ON NORTHEAST FACE UTILITY POLE  
DUE SOUTH 52.88 NORTHWEST CORNER SECTION 30.

Signed by David Pawlaczyk Date 12-24-93

Surveyor's Michigan License No. 17632

ACCEPTED BY THE MACOMB COUNTY  
SURVEY PEER GROUP AS THE OFFICIAL  
CORNER UNDER MICHIGAN PUBLIC ACT 345  
OF 1990 AT A MEETING HELD ON  
12-15-93  
*Frank J. DeDecker*  
FRANK J. DeDECKER, P.S., PE, CHAIRMAN

