

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MACOMB
(County)

Located In: SHELBY Corner Code #
TOWNSHIP

RECORDED IN MACOMB COUNTY
RECORDS AT: 8:30 AM

DEC 30 1993

Register of Deeds Stamp & File Number

- 1. Public Land Survey T 3-N R 12-E M-10
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, DAVID PAWLACZYK in a field survey on NOVEMBER 29, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A POST WAS SET PER GOVERNMENT LAND OFFICE RECORDS,
S. 42° E. 22 LINKS
S. 14° W. 12 LINKS

ACCEPTED BY THE MACOMB COUNTY SURVEY BOARD AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-15-93

[Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing the corner: FRANK DEDECKER, PS, PE, CHAIRMAN

FOUND A 1/2" RE-ROD IN A MONUMENT BOX
PREVIOUS LAND CORNER RECORDATION CERTIFICATE S
LIBER 2208 PAGE 293
LIBER 4055 PAGE 678
AN UNRECORDED AND UNDATED WITNESS SHEET
FROM THE MACOMB COUNTY ROAD COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED THE 1/2" RE-ROD WITH P.A. 345 ALUMINUM CAP STAMPED #17632 ON A 3/4" X 24" IRON ROD.
ACCESSORIES ESTABLISHED

- N. 40° E. 66.64' WITNESS TAG IN UTILITY POL.
- S. 30° E. 76.76' WITNESS TAG IN UTILITY POL.
- S. 85° W. 21.34 WITNESS TAG IN 12" OAK
- N. 70° W. 93.78 & TOP NUT ON HYDRANT

Signed by *[Signature]*
Surveyor's Michigan License No. 17632

Date 12-24-93

