

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in MACOMB (County)

Located In: SHELBY TOWNSHIP Corner Code #

RECORDED IN MACOMB COUNTY RECORDS AT: 8:30 A.M.

DEC 28 1993

Carmella J. Decker CLERK - REGISTER OF DEEDS MACOMB COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

- 1. Public Land Survey T-3-N R-12-E M-11
2. Property Controlling in Section S-T-R
3. Miscellaneous Property in Sec. S-T-R
4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-L and rows 2-13. A dot is present in the cell at row 11, column L.

I, DAVID PAWLACZYK, in a field survey on NOVEMBER 29, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

POST WAS SET PER GOVERNMENT LAND OFFICE RECORDS
N. 05° E. 6 LINKS 36" ELM
N. 34° W. 6 LINKS 32 ELM

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" PIPE IN MONUMENT BOX
PREVIOUS LAND CORNER RECORDATION CERTIFICATES
LIBER 2208, PAGE 297
LIBER 3765, PAGE 514

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-15-93
FRANK J. Decker, PS, PE, CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED 3/4" PIPE WITH P.A. 345 ALUMINUM CAP STAMPED # 17632 ON 3/4" X 24" IRON ROD.
ACCESSORIES ESTABLISHED
N. 45° W. 24.86 WITNESS TAG ON SOUTHWEST FACE UTILITY POLE
N. 60° E. 64.71 WITNESS TAG ON NORTHWEST FACE UTILITY POLE
S. 45° E. 106.99 FOUND CUT CROSS @ TOP OF FIRE HYDRANT
S. 30° W. 67.21 WITNESS TAG ON NORTHWEST FACE UTILITY
DUE SOUTH 36.70 NORTHWEST CORNER SECTION 31

Signed by [Signature] Date 12-24-93
Surveyor's Michigan License No. 17632

