

LIBER 06166P090

B999703

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED IN MACOMB COUNTY RECORDS AT: 8:30 A.M.

For corners in

MACOMB (County)

Located In: SHELBY Twp. Corner Code #

DEC 28 1993

Carmella Amey CLERK - REGISTER OF DEEDS MACOMB COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

- 1. Public Land Survey T-3-N R-12-E M-12
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-L and rows 1-13. Cell (13, 36) contains a black dot.

1. DAVID PAWLACZYK in a field survey on NOVEMBER 29, 1993 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A POST WAS SET PER GOVERNMENT LAND OFFICE RECORDS N. 45° E. 6 LINKS N. 68° W. 21 LINKS

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-15-93. FRANK J. DeDECKER, PS, PE, CHAIRMAN

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND A 1/2" RE-ROD IN MONUMENT BOX PREVIOUS LAND CORNER RECORDATION CERTIFICATES LIBER 4131 PAGE 656 LIBER 5290 PAGE 290

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED THE 1/2" RE-ROD WITH P.A. 345 ALUMINUM CAP STAMPED 17632 ON A 3/4" x 20" IRON ROD

ACCESSORIES ESTABLISHED

N. 30° E. 181.95 S. 45° E. 77.18 S. 45° W. 67.99 N. 20° W. 159.52

TOP NUT ON HYDRANT WITNESS TAG IN UTILITY POLE WITNESS TAG IN 1/2" RE-ROD WITNESS TAG IN 1/2" RE-ROD

Signed by [Signature] Surveyor's Michigan License No. 17632

Date 12-20-93