

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

B997886

For corners in

MACOMB

(County)

Located In:

Corner Code #

SHELBY TWP

1. Public Land Survey

T 3N R 12E

M-13

T _____ R _____

T _____ R _____

T _____ R _____

Seg. # 1 pm

2. Property Controlling
in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

LIBER **06161** PG **236**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, BRUCE ANTCLIFF, in a field survey on NOVEMBER 22, 19 93

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO-Post, NO WITS. REMAIN
MCRC (1934) PLACED IRON-NO WITS REMAIN

MDOT & LCRC (1974) L2500, P794-1" IRON/MON BOX
POWER POLE, N30W, 68.30'
POWER POLE, S25W, 91.98'
TEL. POLE, N25E, 61.00'

EDISON FIELD NOTES (1980)-MON BOX
NAIL IN POLE, N45E, 62.4'
NAIL IN POLE, N45W, 68.1'
NAIL IN POLE, S45W, 91.8'

LCRC (1986) L4080, P891-1/2" BAR IN MON BOX
NW BOLT SIGN POST BASE, SE, 98.66'
SE BOLT SIGN POST BASE, SW, 108.37'
MCRC N&T SE FACE GUY POLE, NE, 62.29'
CONC. NAIL NW FACE UTIL POLE, NW, 68.23'

LCRC (1987) L4131, P656-ROD IN MON BOX
N&T IN UTIL POLE, N05E, 59.47'
N&T IN UTIL POLE, N60E, 118.10'
PK IN UTIL POLE, S50E, 92.30'

THIS CORNER IS COMMON TO ALL FOUR TOWNSHIPS.

LCRC (1991) L5290, P290-1/2" BAR/MON BOX
MDOT N&T SE SIDE PP, WSW, 85.64'
PK SE SIDE PP, SSW, 86.53'
PK SW SIDE PP, NW, 96.53'
PK NW SIDE PP, NE, 91.80'

MDOT (1990)-1/2" IRON IN MON BOX
MDOT N&T IN GUY POLE, N30E, 62.40'
MDOT N&T IN GUY POLE, N30W, 68.35'
NE BOLT SIGN BASE, S40E, 99.58'
MDOT N&T IN PP, S80W, 85.54'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND 1/2" BAR/MON. BOX

FOUND AND VERIFIED ONE OF THE ABOVE WITNESSES

93 DEC 22 AM 9:04

CARMELLA SABAUGH
REGISTER OF DEEDS
MACOMB COUNTY, MI

C. Description of monument for corner and accessories established to perpetuate locating the position of
SET MACOMB COUNTY REMONUMENTATION MARKER AND CAP #25826 IN EXIST. MON. BOX.
WITNESSES

FND NE BOLT SIGN BASE, S47E, 99.57'
SET N&T - PK & MC TAG IN SE FACE P POLE, S57W, 85.85'
SET N&T - PK & MC TAG IN SW FACE P POLE, N44W, 83.59'
SET N&T - PK & MC TAG IN N FACE P POLE, S68E, 149.67'

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by Bruce Antcliff

Date 12-9-93

Surveyor's Michigan License No. 25826

