

APR 29 1996

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

Table with columns: MACOMB (County), Located In: Shelby Twp., Corner Code #. Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 8-15-95

Signature of William E. Soderberg, P.S., CHAIRMAN

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. A dot is marked in the bottom right corner of the grid.

Shelby Twp.

I, George M. Platz, in a field survey on August 10, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- List of survey records including K-13 T.3N.,R.12E. G.L.O. Notes Pgs. 417-420 Joseph Wampler 1817 Set Post, K-1 T.2N.,R.12E. LCRC Liber 2500, Pg. 800 N.C. Jones 1974 1" Iron in Mon. Box, etc.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-13 Set 3/4" Iron Rod with Aluminum Disk Stamped "Macomb County Monument, MI Act 345, #38121" in Location that was Accepted by the Macomb County Remonumentation Peer Group in 1993. Bruce Antcliff, PS #25826, performed the Remonumentation Survey in 1993. The Corner was destroyed in the Spring of 1994 when M-59 was widened. Prior to its destruction, the point was witnessed by Spalding DeDecker & Associates and upon completion of the paving, the point was reset in the same position that was accepted by the Macomb County Remonumentation Peer Group in 1993. This point falls 2651.4' West of the S.1/4 Corner of Section 36, Shelby Twp. T.3N.,R.12E. This point falls 2654.2' East of the S.1/4 Corner of Section 35, Shelby Twp. T.3N.,R.12E.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-13 Southeast Corner of Section 35, Shelby Twp. T.3N.,R.12E. Set 3/4" Iron Rod with Aluminum Disk Stamped "Macomb County Monument, MI Act 345, #38121" in Monument Box located near the Intersection of Schoenherr Road and East Bound M-59. Az. 54° 61.28'; Set Chiseled "+" in the Base Plate of a Steel Traffic Signal Pole, Az. 126° 75.12'; Set Chiseled "+" in the NW Corner of a Square Catch Basin, Az. 212° 65.93'; Set Chiseled "+" in the Base Plate of a Steel Traffic Signal Pole, Az. 344° 113.98'; Set P.K. Nail w/Macomb County Witness Tag in West Face of a Utility Pole

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by George M. Platz Date 9-12-95
Surveyor's Michigan License No. 38121

