

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Macomb (County) Located In: Macomb Twp. Corner Code: A-1
1. Public Land Survey T 3 N R 13 E A-1
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims

RECORDED IN MACOMB COUNTY
RECORDS AT: 8:30 A.M.

DEC 28 1993

Signature of Clerk-Register of Deeds

Register of Deeds Stamp & File Number

I, Huston K. Kennedy, in a field survey on December 14, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-L and rows 2-13. Cell (2,6) contains a dot.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
1817-GLO Wampler, D.S.; Set post; 4" Ironwood N10°W 8 Lns; 3" Ironwood N75°E 8 Lns
1972-Melching, P.S. #14767; LCRC L.2285, Pg.455 - Fnd 1/2" Iron Rod in a monument box (recorded for SW cor Sec 6, Ray Twp (A-13))
1979-Kobs, P.S. #14097; Survey L.3186, Pg.868 - Fnd 1/2" Iron Rod in a monument box
1979-Kobs, P.S. #14097; Survey L.3126, Pg.145 - Fnd 1/2" Iron Rod in a monument box
1991-Fenn, P.S. #23505; LCRC L.5042, Pg.547 - Fnd 1/2" Iron Rod in a monument box (recorded for SW cor Sec 6, Ray Twp (A-13))

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1993 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1/2" Iron Rod in a monument box that is located in the center of Hayes Road, which is gravel surface, and 3' North of 26 Mile Road, which is bituminous surface.

One witness point from the two Certificates of Surveys listed above was found and it was used to recover and verify the found 1/2" Iron Rod in a monument box.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-15-93.
Signature: FRANK J. DeDECKER, PS, PE, CHAIRMAN

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
A-1 I replaced the found 1/2" Iron Rod in a monument box with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623" in a monument box.
N36°E-182.74'-SW corner house #15215
S34°E-39.16'-Set PK Nail & Remon. tag above existing witness in SW face Power Pole
S50°E-97.47'-Set PK Nail & Remon. tag in SW face 11" Elm
S53°W-97.05'-Set PK Nail & Remon. tag in NE face 8" Elm

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.



Signed by [Signature]

Date 12-14-93

Surveyor's Michigan License No. 17623