

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MALCOMB (County)

Located In: MALCOMB TOWNSHIP Corner Code #

RECORDED IN MACOMB COUNTY RECORDS AT: 8:30 A.M.

DEC 28 1993

Register of Deeds Stamp & File Number

- 1. Public Land Survey T-3-N R-13-E A-2
2. Property Controlling in Section S-T-R
3. Miscellaneous Property in Sec. S-T-R

- 4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. Cell (2,6) contains a dot.

DAVID PAWLACZYK in a field survey on DECEMBER 8, 1993 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

NO POST CORNER WAS SET LAND OFFICE RECORDS

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-22-93. FRANK J. DeDECKER, PS, PE, CHAIRMAN

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

THIS CORNER WAS SET AT THE INTERSECTION OF THE WEST LINE OF THE SECTION AND THE EAST/WEST 1/4 LINE AS OCCUPIED. WHILE SETTING THIS CORNER WE FOUND A 1/2" RE-ROD AT 0.22' EAST OF THE CALCULATED CORNER. WE THEN PLACED CORNER ON LINE (M-2) - (M-3), 249.01 FT. SOUTH OF THE E 1/4 CORNER OF SEC. 1 (M-2).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

PLACED P.A. 345 ALUMINUM CAP STAMPED #17632 ON 3/4" x 24" IRON ROD. ACCESSORIES ESTABLISHED; N 45° W. 103.72' WITNESS TAG EAST FACE 10" LOCUST S 60° W. 113.57' N.E. CORNER BLOCK OUTBUILDING N 80° E 34.31' WITNESS TAG SOUTH FACE 18" ELM N 70° E 151.72' N.W. CORNER BRICK HOUSE NORTH 294.01' E 1/4 CORNER OF SECTION 1

Signed by [Signature] Date 12-24-93

Surveyor's Michigan License No. 17632

