

SURVEY & REMONUMENTATION

MAR 17 2000

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION

MACOMB  
(County)

MACOMB TOWNSHIP  
Located In: Corner Code #

- 1. Public Land Survey T 3N R 13E A4  
T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_
- 2. Property Controlling S \_\_\_ T \_\_\_ R \_\_\_  
in Section S \_\_\_ T \_\_\_ R \_\_\_
- 3. Miscellaneous S \_\_\_ T \_\_\_ R \_\_\_  
Property in Sec. S \_\_\_ T \_\_\_ R \_\_\_

1165  
LIBER 9275 PAGE 516  
01/04/2000 09:29:18 A.M.  
MACOMB COUNTY, MI  
CARMELLA SABAUGH, REG/DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, CRAIG P. AMEY, in a field survey on AUGUST 14, 19 99  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- A. 1817 GLO W. PRESTON SET POST
- B. 1989 LCRC, L. 4608, P. 36 J. BAILEY #33963 SET 1" IRON PIPE
- C. 1993 LCRC, L. 6166, P. 71 D. PAWLACZYK #17632 SET 3/4" IRON WITH REMON. CAP IN MONUMENT BOX.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" IRON IN MONUMENT BOX 1.0' BELOW GRAVEL SURFACE IN THE CENTER OF HAYES ROAD

- 5° 132.00' EAST QUARTER POST OF SECTION 12, SHELBY TOWNSHIP (C. 132.00)
- 20° 129.24' FOUND WITNESS TAG ON WEST FACE UTILITY POLE (C. 129.24)
- 150° 46.23' FOUND PK WITH MACOMB COUNTY WITNESS TAG ON THE NORTHEAST FACE OF A UTILITY POLE (C. 46.12)

THE CORNER AGREES WITH WITNESSES IN THE LCRC APPROVED BY THE MACOMB COUNTY REMONUMENTATION PEER GROUP  
ADDITIONAL WITNESSES WERE SET PRIOR TO RECONSTRUCTION OF HAYES ROAD. THE CORNER WAS RESET AND  
REWITNESSED AFTER THE CONSTRUCTION WAS COMPLETED.

DISTANCES TO ADJACENT REMONUMENTATION CORNERS

A4 - A3 2671.40 A4 - A5 2671.49 A4 - M4 (T3N, R12E) 132.02

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 3/4" IRON IN MONUMENT BOX WITH ALUMINUM MACOMB COUNTY REMONUMENTATION CAP #34970

- 20° 129.24' FOUND PK WITH MACOMB COUNTY WITNESS TAG ON THE EAST FACE OF A UTILITY POLE
- 150° 46.23' FOUND PK WITH MACOMB COUNTY WITNESS TAG ON THE NORTHEAST FACE OF A UTILITY POLE
- 295° 55.23' FOUND PK WITH TAG # 30092 IN THE EAST FACE OF A UTILITY POLE
- 355° 132.68' SET MAG NAIL WITH TAG # 30092 IN THE NORTHEAST FACE OF A GUY POLE

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 10/26/99  
William E. Scderberg  
WILLIAM E. SCDERBERG, P.S., CHAIRMAN



Signed by Craig P. Amey Date 12-28-99  
Surveyor's Michigan License No. 34970