

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED IN MACOMB COUNTY
RECORDS AT: 8:30 A.M.

For corners in

MACOMB
(County)

Located in: MACOMB TOWNSHIP Corner Code #

- 1. Public Land Survey T-3-N R-13-E A-5
T ___ R ___
T ___ R ___
T ___ R ___
- 2. Property Controlling S ___ T ___ R ___
in Section S ___ T ___ R ___
- 3. Miscellaneous S ___ T ___ R ___
Property in Sec. S ___ T ___ R ___
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

DEC 28 1993

Frank J. DeDecker
CLERK - REGISTER OF DEEDS
MACOMB COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

I, DAVID PAWLACZYK, in a field survey on NOVEMBER 23, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

NO POST WAS SET PER GOVERNMENT LAND OFFICE RECORDS
CORNER MARKED BY 5" BLACK ASH 147 LINKS SOUTH OF CORNER (M-5)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" METAL ROD IN MONUMENT BOX
PREVIOUS LAND CORNER RECORDATION CERTIFICATES
LIBER 2516, PAGE 86

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED 3/4" METAL ROD WITH P.A. 345 ALUMINUM
CAP STAMPED # 17632 ON 3/4" X 24" IRON ROD.
ACCESSORIES ESTABLISHED

- N. 45° E. 55.92' WITNESS TAG ON WEST FACE UTILITY POLE
- S. 20° E. 61.75' FOUND PAINTED BOLT NORTHEAST SIDE OF MAN HOLE
- S. 45° W. 74.14' WITNESS TAG ON NORTH FACE SAWED OFF UTILITY POLE
- N. 40° W. 142.88' WITNESS TAG ON NORTH FACE UTILITY POLE
- NORTH 98.11' NORTHEAST CORNER SECTION 13 SHELBY TOWNSHIP

Signed by

David Pawlaczyk

Date

12-24-93

Surveyor's Michigan License No.

17632

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-22-93

Frank J. DeDecker
FRANK J. DEDecker, FS, PE, CHAIRMAN