

LIBER 06166P0073

B999686

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED IN MACOMB COUNTY  
RECORDS AT: 8:30 A

For corners in

MACOMB  
(County)

Located in: MACOMB TOWNSHIP Corner Code #

- 1. Public Land Survey T-3-N R-13-E A-6  
T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_
- 2. Property Controlling S \_\_\_ T \_\_\_ R \_\_\_  
in Section S \_\_\_ T \_\_\_ R \_\_\_
- 3. Miscellaneous S \_\_\_ T \_\_\_ R \_\_\_  
Property in Sec. S \_\_\_ T \_\_\_ R \_\_\_

DEC 28 1993

*Frank J. DeDecker*  
CLERK - REGISTER OF DEEDS  
MACOMB COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, DAVID PAWLACZYK, in a field survey on NOVEMBER 24, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

NO POST WAS SET PER GOVERNMENT LAND OFFICE RECORDS  
NO WITNESSES

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND "T" IRON IN GRAVEL ROAD  
PREVIOUS LAND CORNER RECORDATION CERTIFICATES  
LIBER 2527, PAGE 427

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED "T" IRON WITH P.A. 345 ALUMINUM  
CAP STAMPED # 17632 ON 3/4" X 24" IRON ROD  
ACCESSORIES ESTABLISHED  
N. 50° E. 145.12' NORTHWEST CORNER OF HOUSE  
DUE EAST 32.04' WITNESS TAG ON NORTH FACE UTILITY POLE  
S. 45° E. 182.47' NORTHWEST CORNER OF BRICK HOUSE  
S. 20° W. 207.45' WITNESS TAG ON SOUTH FACE 12" ASH  
N. 20° W. 74.21' WITNESS TAG ON EAST FACE 8" ELM  
NORTH 124.22' WEST 1/4 CORNER SECTION 13 SHELBY TOWNSHIP

Signed by *[Signature]*  
Surveyor's Michigan License No. 17632

Date 12-24-93

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-22-93  
*[Signature]*  
FRANK J. DeDECKER, PS, PE, CHAIRMAN

