

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED IN MACOMB COUNTY  
RECORDED AT: 8:30 A.M.

For corners in

MACOMB  
(County)

Located In: MACOMB Twp. Corner Code #

DEC 28 1993

*Larnelle A. ...*  
CLERK - REGISTER OF DEEDS  
MACOMB COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

- 1. Public Land Survey T-5-NR-13-E A-7  
T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_
- 2. Property Controlling S \_\_\_ T \_\_\_ R \_\_\_  
in Section S \_\_\_ T \_\_\_ R \_\_\_
- 3. Miscellaneous S \_\_\_ T \_\_\_ R \_\_\_  
Property in Sec. S \_\_\_ T \_\_\_ R \_\_\_
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

|    | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |   |

I, DAVID PAWLACZYK a field survey on NOVEMBER 24, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A POST WAS SET PER GOVERNMENT LAND OFFICE RECORDS  
N. 60° W. 26 LINKS  
S. 78° E. 10 LINKS

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-22-93

*Frank J. DeDecker*  
FRANK J. DeDECKER, PS, PE, CHAIRMAN

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND A 1/2" RE-ROD IN A MONUMENT BOX. THIS MARKER FALLS 0.13' WEST OF LINE (EAST TOWNSHIP LINE). WE REMOVED THE 1/2" RE-ROD AND SET THE PRESCRIBED IRON AND CAP ON THE TOWNSHIP LINE. THIS MARKER FALLS 152.79' SOUTH OF THE NORTHEAST CORNER OF SECTION 24, SHELBY TOWNSHIP

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED 1/2" RE-ROD WITH P.A. 345 ALUMINUM CAP STAMPED #17632 ON A 3/4" X 24" IRON ROD.

ACCESSORIES ESTABLISHED

|           |         |                                  |
|-----------|---------|----------------------------------|
| N. 20° E. | 108.77' | WITNESS TAG IN UTILITY POLE      |
| S. 30° E. | 49.85'  | WITNESS TAG IN UTILITY POLE      |
| WEST      | 48.67'  | WITNESS TAG IN UTILITY POLE      |
| N. 15° W. | 211.81' | WITNESS TAG IN UTILITY POLE      |
| NORTH     | 152.79' | N-E CORNER OF SECTION 24, SHELBY |

Signed by *[Signature]*  
Surveyor's Michigan License No. 17632

Date 12-24-93

