

LIBER 061668075

R999688

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED IN MACOMB COUNTY
RECORDS AT: 8:30 A.M.

For corners in

MACOMB (County)

Located In: MACOMB TOWNSHIP Corner Code #

DEC 28 1993

Signature of Clerk: CLERK - REGISTER OF DEEDS MACOMB COUNTY

Register of Deeds Stamp & File Number

- 1. Public Land Survey T-3-N R-13-E A-8
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

- 4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. Cell (8,19) contains a dot.

I, DAVID PAWLACZYK, in a field survey on DECEMBER 14, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

NO POST WAS SET PER GOVERNMENT LAND OFFICE RECORDS
NO WITNESSES

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" RE-ROD
PREVIOUS LAND CORNER RECORDATION CERTIFICATES
LIBER 3217, PAGE 913
LIBER 4983, PAGE 763

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-22-93
FRANK J. DeDECKER, PS, PE, CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED 1/2" RE-ROD WITH P.A. 345 ALUMINUM CAP STAMPED # 17632 ON 3/4" x 24" IRON ROD.
ACCESSORIES ESTABLISHED
N. 80° E. 37.84' WITNESS TAG ON NORTHWEST FACE 30" MAPLE
S. 45° W. 114.98' NORTHWEST CORNER OF HOUSE
S. 50° W. 104.99' SOUTHEAST CORNER OF GARAGE
N. 45° E. 147.01' NORTHEAST CORNER OF GARAGE
NORTH 155.58' EAST 1/4 CORNER SECTION 24 SHELBY TOWNSHIP

Signed by [Signature] Date 12-24-93
Surveyor's Michigan License No. 17632

