

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MACOMB
(County)

Located In: MACOMB
TOWNSHIP Corner Code #

RECORDED IN MACOMB COUNTY
RECORDS AT: 8:30 A.M.

DEC 28 1993

[Signature]
CLERK - STATE OF DEERS
MACOMB COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

- 1. Public Land Survey T-3-N R-13-E A-10
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling in Section S _____ T _____ R _____
S _____ T _____ R _____
- 3. Miscellaneous Property in Sec. S _____ T _____ R _____
S _____ T _____ R _____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							

I, DAVID PAWLACZYK, in a field survey on NOVEMBER 29, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

NO POST WAS SET PER GOVERNMENT LAND OFFICE RECORDS
NO WITNESSES

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" PIPE IN GRAVEL ROAD
PREVIOUS LAND CORNER RECORDATION CERTIFICATES
LIBER 2208, PAGE 291
LIBER 3218, PAGE 56

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED THE 1/2" PIPE WITH P.A. 345 ALUMINUM
CAP STAMPED # 17632 ON 3/4" x 24" IRON ROD
ACCESSORIES ESTABLISHED
N. 20° E., 112.14' WITNESS TAG ON EAST FACE UTILITY POLE
S. 60° E., 39.23' WITNESS TAG ON SOUTHWEST FACE UTILITY POLE
N. 50° W 114.51' @ TOP NUT FIRE HYDRANT
N. 30° W. 50.61' WITNESS TAG ON SOUTHWEST FACE 12" OAK
NORTH 50.04' EAST 1/4 CORNER SECTION 25 SHELBY TOWNSHIP

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-22-93
[Signature]
FRANK J. DeDECKER, PS, PE, CHAIRMAN

Signed by [Signature]

Date 12-24-93

Surveyor's Michigan License No. 17632