

LIBER 06166N078

B999691

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED IN MACOMB COUNTY
RECORDS AT: 8:30 A.M.

For corners in

MACOMB
(County)

Located In: MACOMB TOWNSHIP Corner Code #

DEC 28 1993

Signature of Clerk - Register of Deeds
MACOMB COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

- 1. Public Land Survey T-3-N R-13-E A-11
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13, containing numbers 1-36.

I, DAVID PAWLACZYK, in a field survey on 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

POST WAS SET PER GOVERNMENT LAND OFFICE RECORDS
N. 02° W. 23 LINKS 20" ELM
N. 73° W. 25 LINKS 18" ELM

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" RE-ROD IN MONUMENT BOX
PREVIOUS LAND CORNER RECORDATION CERTIFICATES
LIBER 2208, PAGE 295
LIBER 3059, PAGE 200
FOUND 1/2" RE-ROD 0.03' WEST OF LINE
REPLACED WITH 3/4" IRON ROD ON LINE M-11 TO M-12

SEATED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-22-93
Signature of Frank J. DeDecker, P.S., P.E., Chairman

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED 1/2" RE-ROD WITH P. A. 345 ALUMINUM CAP STAMPED # 17632 ON 3/4" x 24" IRON ROD
ACCESSORIES ESTABLISHED
N. 45° E. 48.12 CUT CROSS TOP NUT OF FIRE HYDRANT
S. 60° E. 80.04 CUT CROSS TOP NUT OF FIRE HYDRANT
S. 45° W. 35.59 WITNESS TAG ON NORTHWEST FACE UTILITY POLE
N. 30° W. 57.21 WITNESS TAG ON SOUTHWEST FACE UTILITY POLE
NORTH 36.78 NORTHEAST CORNER SECTION 36

Signed by [Signature]
Surveyor's Michigan License No. 17632

Date 12-24-93