

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Macomb Located In: Macomb Twp Corner Code # \_\_\_\_\_  
 (County)

1. Public Land Survey T 3N R 13E \_\_\_\_\_ B-1 \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

**SURVEY &  
 REMONUMENTATION**

FEB 27 1997

**COMMISSION**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
1	•											
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert D. Kohn, in a field survey on November 30, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

1817	Corner not set	W. Preston	N/A	GLO Notes
1973	Not found or set	C. Melching	#14767	L2428 P116 Survey
1992	Not found or set	G. James	#19835	L5625 P260 Survey
1995	Set mag nail	J. Wright	#40165	Unrecorded Survey Sketch
				Urban Land Consultants
				Job #940826-3994

ACCEPTED BY THE MACOMB COUNTY SURVEY PEEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 8-20-96  
William E. Soderberg  
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

A P.K. Nail in asphalt pavement was found on line between the township corner (A-1) and the south 1/4 corner of Section 31 Ray Twp. (B-13). 3 Witness ties match accessories from Urban Land Consultants Survey #940826-3994.

The following field measurements were made:

A-1 to B-1	1921.28 meas.	
	1921.54 rec.	Urban Land Consultants Survey #940826-3994
B-1 to C-1	2690.26 meas.	
	2690.29 rec.	Urban Land Consultants Survey #940826-3994
A-1 to C-1	4611.54 meas.	
	4611.83 rec.	Urban Land Consultants Survey #940826-3994
	4610.85 rec.	L2428 P116 Survey



**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

The found P.K. nail in asphalt pavement was replaced with a 3/4" x 24" iron rod with a 2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #26459" in a new monument box. Witnesses are as follows:

N. 30°E.,	27.58'	Set nail and Macomb Co. remon washer in W. face 12" Box Elder
N. 45°W.,	39.28'	Set nail and Macomb Co. remon. washer in W. face 8" Elm
S. 30°E.,	58.47'	Set nail and Macomb Co. remon. washer in E. face 30" Walnut
N. 71°E.,	78.01'	Mac Co. GPS Control Mon. #1993-12
Due East	64.48'	Mac. Co. remon cap #26459 and iron rod in mon box (B-13) Ray Twp.

The selected location is accepted by me and generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by Robert D. Kohn Date November 30, 1996  
 Surveyor's Michigan License No. #26459