

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED IN MACOMB COUNTY
RECORDS AT: 8:30 A.M.

For corners in

MACOMB

(County)

Located In:

Corner Code #

MACOMB TWP.

1. Public Land Survey

T 3N R 13E

B-13

T R

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

4. Lot No. , Recorded Plat

5. Private Claims

DEC 28 1993

Signature of Clerk - Register of Deeds

Register of Deeds Stamp & File Number

I, BRUCE ANTCLIFF, in a field survey on NOVEMBER 23, 19 93

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO-Post, NO WITS. REMAIN

LCRC (1978) L2940,P349-PK NAIL
N&T UTIL POLE, NE'LY, 61.62'
PK IN 12" TREE, SE'LY, 112.18'
PK IN UTIL POLE, NWLY, 117.72'

LCRC (1979) L3184,P576-PK IN CENTERLINE OF ROAD
MDOT N&T IN MBT POLE, NE, 61.62'
PK NAIL TOP OF CURB, SE, 30.53'
PK NAIL TOP OF CURB, SW, 47.18'
PK NAIL MBT POLE, NW, 117.75'
IRON, WEST, 2086.41'

LCRC (1988) L4790,P790-PK NAIL
PK NW FACE GUY POLE, N41E, 62.60'
PK N FACE UTIL POLE, S29E, 59.43'
PK N FACE UTIL POLE, S40W, 78.73'
PK S FACE UTIL POLE, N60W, 117.63'
SW SEC COR., WEST, 2086.54'

MDOT (1988)-PK NAIL
HOR. CONTROL MON #21, S50E, 58.10'
PK IN UTIL POLE, S50E, 92.30'
MDOT N&T IN PP, S50W, 78.66'
MDOT N&T IN GUY POLE, N25E, 64.20'
"X" IN SE RIM MH, N35W, 58.33'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND PK NAIL

FOUND AND VERIFIED THREE OF THE ABOVE WITNESSES

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 34 OF 1990 AT A MEETING HELD ON 12-1-93
FRANK J. DeDECKER, PS, PE, CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 5/8" REBAR AND CAP #25826; I GUARANTEE TO SET MONUMENTATION CAP AND MON. BOX WHEN THE NEW PAVEMENT IS INSTALLED NEXT YEAR.

WITNESSES

FND MDOT N&T NW FACE P POLE, S51W, 78.68'
FND "X" IN SE RIM MH, N37W, 58.63'
FND PK NW FACE GUY POLE, N43E, 62.16'
SET N&T - PK & MC TAG IN NE FACE P POLE, S27E, 59.90'

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by Bruce Antcliff

Date 12-13-93

Surveyor's Michigan License No. 25826

