

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MACOMB (County)

Located In: MACOMB TOWNSHIP Corner Code #

RECORDED BY MACOMB COUNTY RECORDED AT: 8:30 A.M.

DEC 28 1993

Clerk - Register of Deeds MACOMB COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

- 1. Public Land Survey T-3-N R-13-E C-4
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

- 4. Lot No. Recorded Plat
5. Private Claims

DAVID PAWLACZYK in a field survey on DECEMBER 8, 1993 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-L and rows 1-13. A dot is marked at row 4, column C.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

NO POST WAS SET PER GOVERNMENT LAND OFFICE RECORDS CORNER MARKED BY 6" WHITE ASH NO WITNESSES

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" RE-ROD WITH CAP # 16052 IN GRAVEL ROAD PREVIOUS LAND CORNER RECORDATION CERTIFICATES LIBER 3074 PAGE 501 LIBER 3055 PAGE 824

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-15-93 FRANK J. DeDECKER, PS, PE, CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED THE 1/2" RE-ROD WITH P.A. 345 ALUMINUM CAP STAMPED # 17632 ON 3/4" X 24" IRON ROD. ACCESSORIES ESTABLISHED

DUE WEST 60.00 1/2" RE-ROD AT MONUMENT N. 20° E. 21.98 WITNESS TAG ON NORTH FACE CLUMP 2" ASH N. 80° E. 14.68 WITNESS TAG ON NORTH FACE 6" ELM S. 20° E. 57.10 WITNESS TAG ON EAST FACE 8" ASH

Signed by [Signature] Date 12-24-93 Surveyor's Michigan License No. 17632

