

LIBER 081660095

B999703

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MACOMB (County)

Located In: MACOMB TOWNSHIP Corner Code #

RECORDED IN MACOMB COUNTY RECORDS AT: 8:30 A.M.

DEC 28 1993

Signature of Clerk: CLERK - REGISTER OF DEEDS MACOMB COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

- 1. Public Land Survey T-3-N R-13-E C-5
2. Property Controlling In Section S-T-R
3. Miscellaneous Property in Sec. S-T-R
4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. A dot is marked at row 5, column C.

I, DAVID PAWLACZYK in a field survey on NOVEMBER 23, 1993 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

POST WAS SET PER GOVERNMENT LAND OFFICE NOTES N.53°E. 13 LINKS 7" BLACK OAK N.70°W. 13 LINKS 12" BLACK ASH

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" RE-ROD IN MONUMENT BOX PREVIOUS LAND CORNER RECORDATION CERTIFICATE LIBER 4716 PAGE 612 LIBER 2964 PAGE 813

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED THE 1/2" RE-ROD WITH P.A. 349 ALUMINUM CAP STAMPED #17632 ON 3/4" x 24" IRON ROD. ACCESSORIES ESTABLISHED:

- N. 60°W 141.38' FOUND S.W.M. NAIL AND WASHER S. FACE U-POLE
N. 20° E. 54.63' WITNESS TAG E. FACE U-POLE
N. 45° E. 49.43' FOUND CUT CROSS & TOP NUT FIRE RESISTANT WITNESS TAG SOUTH FACE U-POLE
N. 80° E. 186.51'

Signed by [Signature] Date 12-28-93 Surveyor's Michigan License No. 17632

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-15-93 FRANK J. DeDECKER, PS, PE, CHAIRMAN

