

LIBER 06166PG014

B999627

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED IN MACOMB COUNTY RECORDS AT: 8:30 A.M.

For corners in

MACOMB

(County)

Located In:

Corner Code --

MACOMB TWP.

1. Public Land Survey

T 3N R 13E

D-13

T R

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous

S T R

Property in Sec.

S T R

4. Lot No. , Recorded Plat

5. Private Claims

DEC 28 1993

Signature of Clerk - Register of Deeds, Macomb County, Michigan

Register of Deeds Stamp & File Number

Grid table with columns A-L and rows 2-13. Cell 10,3 contains a dot.

BRUCE ANTCLIFF

NOVEMBER 23

19 93

I, BRUCE ANTCLIFF, in a field survey on NOVEMBER 23, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO-Post, NO WITS. REMAIN

LCRC (1989) L4723, P608-PK NAIL N02E-61.20'-PK NAIL IN E. SIDE UTIL POLE S03W-58.54'-PK NAIL IN W. SIDE UTIL POLE S71W-158.81'-PK NAIL IN NW SIDE UTIL POLE

LCRC (1978) L2940, P350-PK NAIL PK NAIL IN UTIL POLE N'LY 61.24' PK NAIL IN UTIL POLE S'LY 58.55' PK IN UTIL POLE SW'LY 158.80'

REC. SURVEY (1979) L3199, P926-PK NAIL PK IN DE POLE, NORTH, 61.25 N. EDGE OF PAVT., NORTH, 16.00' PK IN DE POLE, SOUTH, 58.56' TOP HYDRANT, SW, 218.75'

MDOT (1988)-PK NAIL N15W 51.28'-TOP CENTER OF FIRE HYDRANT S12W-58.28'-MDOT NAIL & CAP IN PP S50W-89.52'-MDOT NAIL & CAP IN 4" ELM N44W-90.36'-MDOT NAIL & CAP IN SW COR. WOOD FENCE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND PK NAIL

FOUND AND VERIFIED THREE OF THE ABOVE WITNESSES

VERIFIED MDOT DISTANCES TO C-13 AND E-13, T3N, R13E AND TO C-1, T2N, R13E

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 5/8" REBAR AND CAP #25826; I GUARANTEE TO SET MONUMENTATION CAP AND MON. BOX WHEN THE NEW PAVEMENT IS INSTALLED NEXT YEAR. WITNESSES

FND MDOT N&T IN W FACE P POLE, S06W, 58.29' FND MDOT N&T IN NW FACE 4" ELM, S53W, 89.52' FND PK IN NW FACE P POLE, S73W, 158.88' SET "+" IN W RIM MH, N05E, 35.64' SET "+" IN N RIM MH, N66W, 106.42'

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by Bruce Antcliff

Date 12-13-93

Surveyor's Michigan License No. 25826

ACCEPTED BY THE MACOMB COUNTY SURVEY PER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-1-93 FRANK J. DODECKER, P.S. PE, CHAIRMAN

