

LIBER 06166PG099

B999712

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MACOMB (County)

Located In: MACOMB TWP.

Corner Code #

RECORDED IN MACOMB COUNTY RECORDS AT: 8:30 A.M.

DEC 28 1993

Register of Deeds Stamp & File Number

- 1. Public Land Survey T-3 N R-13-E E-9
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. , Recorded Plat
5. Private Claims

I, DAVID PAWLACZYK, in a field survey on NOV. 29, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-L and rows 2-13. A dot is marked at the intersection of column C and row 9.

A. Description of original monument and accessories and/or subsequent restoration:

Post WAS SET PER GOVERNMENT LAND OFFICE RECORDS S 32° E, 11 LKS. 36" WHITE OAK S 58° W, 13 LKS 5" BEECH

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" RE-ROD IN ASPHALT ROAD PREVIOUS LAND CORNER RECORDATION CERTIFICATES LIBER 5063 PAGE 829 LIBER 4723 PAGE 614 LIBER 4718 PAGE 613 LIBER 2844 PAGE 956 LIBER 2268 PAGE 701

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-15-93 FRANK J. DeDECKER, PS, PE, CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED THE 1/2" RE-ROD WITH P. A. 345 ALUMINUM CAP STAMPED # 17632 ON 3/4" x 24" IRON ROD.

ACCESSORIES ESTABLISHED

- N. 50° W, 58.87 SOUTHEAST BUILDING CORNER
N 40° E, 48.65 FOUND CUT CROSS FIRE HYDRANT
S, 45° E, 48.10 FOUND NORTHWEST BUILDING CORNER
S: 45° E, 41.70 WITNESS TAG, SOUTH FACE UTILITY POLE
S. 75° W, 104.51 WITNESS TAG ON NORTH FACE UTILITY POLE

Signed by [Signature] Surveyor's Michigan License No. 17632

Date 12-24-93

