

B997893

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

93 DEC 22 AM 9:05
CARMELLA SABAUGH
REGISTER OF DEEDS
MACOMB COUNTY, MI

For corners in

MACOMB

(County)

Located In:

Corner Code #

MACOMB TWP.

- 1. Public Land Survey T 3N R 13E E-13
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Def. 1 pm

LIBER 06161 PC248

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, BRUCE ANTCLIFF in a field survey on NOVEMBER 23, 19 93

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO-Post, NO WITS, REMAIN

LCRC (1972) L2302.P904- MON BOX
SW'LY RIM STORM MH, N45E, 40.00'
SE'LY RIM STORM MH, N45W, 41.65'
PK IN DE POLE, S45W, 69.55'

MDOT & LCRC(1988) L4507,P853-IRON/MON BOX
MDOT N&T IN PP, N38E, 72.42'
MDOT N&T IN PP, N27W, 66.38'
MDOT N&T IN PP, S36W, 70.50'
N&T IN TEL POLE, S11E, 113.17'
PK NAIL, WEST, 2670.82'

LCRC (1991) L5290.P292-1/2" IRON #31610
IN MON BOX
PK/DISK #21563 NW SIDE PP, NE, 72.51'
PK IN SIDEWALK, SE, 75.01'
PK/DISK #21563 SW SIDE PP, NW, 66.58'
PK/DISK #21563 NW SIDE PP, SW, 70.48'

LCRC (1978) L2940.P350-IRON IN MON BOX
PK&T IN UTIL POLE, NE'LY, 72.55'
MDOT N&T IN UTIL POLE, SE'LY, 113.14'
MDOT N&T IN UTIL POLE, SE'LY, 69.63'
PK&T IN UTIL POLE, NW'LY, 66.64'

LCRC (1989) L4723.P608-EMPTY MON BOX
PK/DISK #21563 W SIDE PP, N37E, 72.32'
PK/DISK #21563 N SIDE PP, S73E, 120.89'
PK/DISK #21563 NW SIDE PP, S33W, 70.67'
PK/DISK #21563 SW SIDE PP, N37W, 66.45'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" ROD W/MDOT CAP IN MON. BOX

FOUND AND VERIFIED THREE OF THE ABOVE WITNESSES

VERIFIED MDOT DISTANCES TO D-13, T3N, R13E AND TO E-1, T2N, R13E

C. Description of monument for corner and accessories established to perpetuate locating the position of

SET MACOMB COUNTY REMONUMENTATION MARKER AND CAP #25826 IN EXIST. MON. BOX.
WITNESSES

FND MDOT N&T IN SE FACE P POLE, N37E, 72.36'
FND MDOT N&T IN E FACE P POLE, N28W, 66.38'
FND MDOT N&T IN SE FACE P POLE, S33W, 70.48'
SET N&T -PK & MC TAG IN NW FACE P POLE, S37E, 79.22'

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by Bruce Antcliff

Date 12-9-93

Surveyor's Michigan License No. 25826

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-1-93.
FRANK J. DÖCKER, PS, PE, CHAIRMAN

