

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MACOMB
(County)

Located In: MACOMB Twp. Corner Code #:

RECORDED IN MACOMB COUNTY
RECORDS AT: 8:30 A

DEC 28 1993

Lester J. Decker
CLERK - REG. OF LAND
MACOMB COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

- 1. Public Land Survey T-3-N R-13-E 6 10
T R
T R
T R
- 2. Property Controlling S T R
in Section S T R
- 3. Miscellaneous S T R
Property in Sec. S T R
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, DAVID PAWLACZYK, in a field survey on NOVEMBER 29, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

POST WAS SET PER GOVERNMENT LAND OFFICE RECORDS
S. 65° W. 21 LINKS 14" ELM
N. 33° E. 21 LINKS 10" BLACK ASH

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SET 1/2" RE-ROD FROM 3 ACCESSORIES LIBER 2522 PAGE 271
PREVIOUS LAND CORNER RECORDATION CERTIFICATES
LIBER 2522 PAGE 271
LIBER 2412 PAGE 928
LIBER 4723 PAGE 610

ACCEPTED BY THE MACOMB COUNTY
SURVEY PEER GROUP AS THE OFFICIAL
CORNER UNDER MICHIGAN PUBLIC ACT 34:
OF 1990 AT A MEETING HELD ON
12-15-93
Frank J. Decker
FRANK J. DeDECKER, PS, PE, CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED THE 1/2" RE ROD WITH P.A. 345 ALUMINUM
CAP STAMPED #17632 ON 3/4" X 24" IRON ROD.
ACCESSORIES ESTABLISHED

N. 45° E. 37.76'
S. 83° E. 67.36'
S. 48° W. 36.42'
DUE WEST 31.45'

WITNESS TAG IN UTILITY POLE
WITNESS TAG IN UTILITY POLE
WITNESS TAG IN UTILITY POLE
& 3" METAL SIGN

Signed by *David Pawlaczyk*
Surveyor's Michigan License No. 17632

Date 12-24-93

