

LIBER 05166PG103

B999716

LAND CORNER RECORDATION CERTIFICATE RECORDED IN MACOMB COUNTY
Filing Requirement of Act 74, Mich. P.A. 1970 RECORDS AT: 8:30 AM

For corners in

MACOMB
(County)

Located In: MACOMB
TWP

Corner Code #

- 1. Public Land Survey T-3-NR-13-E G-12
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling in Section S _____ T _____ R _____
S _____ T _____ R _____
- 3. Miscellaneous Property in Sec. S _____ T _____ R _____
S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

DEC 28 1993
Larnelle [Signature]
CLERK - REGISTER OF DEEDS
MACOMB COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

I, DAVID PAWLACZYK, in a field survey on NOVEMBER 29, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	I
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

POST WAS SET PER GOVERNMENT LAND OFFICE RECORDS
N. 70° E. 15 LINKS 18" BEECH
S. 25° W. 6 LINKS 6" BEECH

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND BENT 1/2" RE-ROD IN MONUMENT BOX
PREVIOUS LAND CORNER RECORDATION CERTIFICATES
LIBER 2548 PAGE 980
LIBER 3179 PAGE 739
LIBER 4369 PAGE 435
LIBER 4790 PAGE 793

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-15-93
[Signature]
FRANK J. DEDECKER, FS, PE, CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED THE 1/2" RE-ROD WITH P.A. 345 ALUMINUM CAP STAMPED # 17632 ON 3/4" x 24" IRON ROD.
ACCESSORIES ESTABLISHED
N. 80° W. 100.21 SOUTHEAST CORNER OF HOUSE
N. 40° E. 60.55 WITNESS TAG ON NORTHWEST FACE UTILITY POLE
S. 30° W. 83.00 WITNESS TAG ON SOUTHEAST FACE 20" MAPLE
S. 45° W. 44.74 WITNESS TAG ON NORTH FACE 10" PINE

Signed by [Signature]
Surveyor's Michigan License No. 17632

Date 12-24-93

