

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

**SURVEY &
 REMONUMENTATION**

APR 07 1998

SECTION

For corners in

Macomb
 (County)

Located in: Macomb Twp. Corner Code # _____

1. Public Land Survey T 3-N R 13-E H-1
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ F C0623815 LIBER:07784 PAGE:392 08:57A 12/22/1997
 in Section S _____ T _____ F CARMELLA SABAUGH-MACOMB COUNTY, MI REG/DEEDS

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, John N. Redash, in a field survey on October 16, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

| | | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | |

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

| | | | | | |
|------|-----------------------|--------------|------------|--------|-------------|
| 1817 | Not set | G.L.O. Notes | W. Preston | N/A | N/A |
| 1979 | P.K. Nail in pavement | L.C.R.C. | H. Kobs | #14097 | L3186, P870 |
| 1979 | P.K. Nail in pavement | Survey | H. Kobs | #14097 | L3186, P879 |
| 1989 | P.K. Nail in pavement | Survey | D. King | #30085 | L4866, P823 |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No corner found at above described position. A P.K. Nail was set in asphalt pavement from witnesses on L.C.R.C. (L3186, P870). Field observations were obtained between the following corners and found nail following 0-31 north of line H-13 - G-13. Further set nail 0.31 south and on line H-13 to G-13.

| | | |
|----------------------------------|---------------------------------|-------------------------------|
| G-1 to H-1 | H-1 to I-1 | H-1 to H-13 |
| 2690.53 meas. | 2689.86 meas. | 87.22 meas. |
| No G.L.O. | No. G.L.O. | 87.52 Rec. Survey L4866, P823 |
| 2690.35 Rec. Survey, L4866, P823 | 2689.92 Rec. Survey L3186, P879 | 87.52 Rec. Survey L3186, P879 |
| | | No. G.L.O. |

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I replaced the set P.K. Nail with a 3/4" X 24" iron rod with a 2" aluminum disk stamped "Macomb County Monument MI Act 345 #37281" in a new monument box in asphalt pavement. Witness ties are as follows:

| | | |
|------------|--------|---|
| Due East | 87.22' | Macomb County Remon. Cap #37281 and iron in monument box (H-13) T-4-N., R-13-E. |
| S. 50° E., | 55.70' | Set P.K. nail and Macomb County Remon. tag N.E. face 48" Oak |
| S. 26° E., | 38.91' | Cross in west face of 6" steel post |
| S. 25° W., | 34.15' | Cross in east face of 6" steel post |



The selected location is accepted by me and generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by John N. Redash
 Surveyor's Michigan License No. 37281

Date December 16, 1997

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983
 REVISED OCT., 1996

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 11-18-97
William E. Soderberg
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

695