

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1997901

For corners in

<u>MACOMB</u> (County)	Located In:	Corner Code #/
	<u>MACOMB TWP.</u>	
1. Public Land Survey	T <u>3N</u> R <u>13E</u>	<u>H-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

LIBER **06161** PD **251**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, BRUCE ANTCLIFF, in a field survey on NOVEMBER 23, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 GLO-Post, NO WITS. REMAIN

MDOT & LCRC (1988) L4578, P431-PK NAIL
 "X" S RIM WATER MH, N05E, 53.00'
 TOP CENTER HYDRANT, N26E, 48.28'
 S35E, "X" S RIM WATER MH, S35E, 53.06'
 TOP CENTER HYDRANT, S15E, 52.86'
 "X" S RIM STORM MH, S35E, 73.41'
 MDOT N&T IN 12" ASH, N65W, 53.64'

SODERBERG FIELD NOTES (1988) PK NAIL
 CENTERLINE OF HYDRANT, NNE, 48.33'
 SE COR ROAD C.B., NW, 48.97'
 CENTER HYDRANT, SSE, 52.85'
 BACK OF CURB, NORTH, 24.12'
 PK & T#17635 TOP OF CURB, NE, 26.61'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND PK NAIL
 FOUND AND VERIFIED SIX OF THE ABOVE WITNESSES.

93 DEC 22 AM 9:05

CARMELLA SABAUGH
 REGISTER OF DEEDS
 MACOMB COUNTY, MI

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-1-93

Frank J. Decker
 FRANK J. DECKER, PS, PE, CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET MACOMB COUNTY REMONUMENTATION MARKER AND CAP #25826 IN NEW MON BOX WITNESSES

FND "X" S RIM WATERGATE MH, N10E, 53.00'
 TOP CENTER HYDRANT, N32E, 48.22'
 FND "X" S RIM WATERGATE MH, S30E, 53.18'
 TOP CENTER HYDRANT, S10E, 52.99'
 FND "X" S RIM STORM MH, S42W, 73.44'
 FND PK&T#17635 TOP OF CURB, N32E, 26.62'



The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by Bruce Antcliff Date 12-9-93

Surveyor's Michigan License No. 25826