

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

**SURVEY &
 REMONUMENTATION**

APR 07 1998

SECTION

For corners in

Macomb
 (County)

Located In: Macomb Twp. Corner Code #

1. Public Land Survey		<u>T-3-N</u> <u>R-13-E</u>	<u>I-1</u>
		T_____ R_____	_____
		T_____ R_____	_____
		T_____ R_____	_____
2. Property Controlling in Section	S_____	T_____ R_____	_____
	S_____	T_____ R_____	_____
3. Miscellaneous Property in Sec.	S_____	T_____ R_____	_____
	S_____	T_____ R_____	_____

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-18-97

William E. Soderberg, P.S., Chairman
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, John N. Redash, in a field survey on October 16, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

1817	3" Diameter Hornbean	G.L.O. Notes	W. Preston	N/A	
1977	P.K. Nail and washer	Survey	G. James	#19835	L2811, P167
1978	P.K. Nail	Survey	G. James	#19835	L3010, P271
1979	P.K. Nail and washer	Survey	H. Kobs	#14097	L3186, P879
1979	P.K. Nail and washer	L.C.R.C.	H. Kobs	#14097	L3186, P870
1991	P.K. Nail and washer	Survey	D. King	#30085	L5778, P394
1993	P.K. Nail and washer	L.C.R.C.	D. King	#30085	L5778, P411

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A P.K. Nail and washer 0.35' below top of pavement and 2.3' north of centerline of 26 Mile Road currently occupies this corner. The following witness ties were used to recover and verify its position: 2 ties match current measurements from L.C.R.C. L3186, P870, and 4 ties match witnesses from both L.C.R.C. (L5778, P411) and Survey (L5778, P394). Field observations were obtained between the following corners and falls on line between H-13 and I-13:

H-1 to I-1	I-1 to J-1	I-1 to I-13
2689.86' meas.	2720.77 meas.	100.72 meas.
No. G.L.O.	No. G.L.O.	105.60 Rec. G.L.O.
2689.92 Rec. Survey L3186, P879	2721.01 Rec. Survey L5778, P394	100.62 Rec. Survey L5778, P394
	2720.60 Rec. Survey L2811, P167	100.58 Rec. Survey L3010, P271

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I replaced the found P.K. Nail and washer in asphalt pavement with a 3/4" X 24" iron rod with a 2" aluminum cap stamped "Macomb County Monument MI Act 345 #37281" in a new monument box. Witness ties are as follows:

N. 42° E.	81.96'	Set P.K. Nail and Macomb County Remon. Washer N.W. face 6" Ash
N. 39° W.,	42.09'	Set P.K. Nail and Macomb County Remon. washer N.E. face U-pole
S. 45° W.,	98.69'	Set P.K. Nail and Macomb County Remon. washer N.W. face 12" Elm
S. 48° W.,	43.74'	Set P.K. Nail and Macomb County Remon. washer N.W. face 8" Elm
Due East	100.72'	Macomb County Remon. Cap and monument box (I-13, T-4-N, R-13-E.)

The selected location is accepted by me and generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by John N. Redash
 Surveyor's Michigan License No. 37281

Date December -16, 1997



in 91p