


LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Macomb Located In: Macomb Twp. Corner Code #
(County)

- 1. Public Land Survey T-3-N R-13-E 1-3
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling in Section S _____ T _____ R _____
 S _____ T _____ R _____
- 3. Miscellaneous Property in Sec. S _____ T _____ R _____
 S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____



SURVEY &
 REMONUMENTATION

MAR 15 1999

SECTION

Register of Deeds Stamp & File Number

I, John N. Redash, in a field survey on Jan. 6, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | ● | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

| Year | Description | G.L.O. Notes | W. Preston | N/A | N/A |
|------|------------------------------|--------------|-------------|--------|-------------|
| 1817 | Set post | | | | |
| 1975 | Found 1/2" iron | Survey | G. Avendt | #16034 | L2605, P593 |
| 1975 | Found 1/2" iron | L.C.R.C. | G. Avendt | #16034 | L2605, P594 |
| 1980 | Found 1/2" iron | L.C.R.C. | K. Thompson | #16054 | L3245, P395 |
| 1993 | Found 1/2" iron in hand hole | L.C.R.C. | R. Stecker | #30103 | L5767, P680 |
| 1995 | 1/2" Iron | L.C.R.C. | D. King | #30085 | L6586, P204 |
| 1995 | 1/2" bar | L.C.R.C. | J. Wright | #40165 | L6832, P273 |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A 1/2" iron rod 0.3' below asphalt top of pavement currently occupies this corner at the intersection of 25 Mile Road and Card Road. The following witness ties were used to recover and verify its position: Current measurements match 2 ties from L.C.R.C.s L2605, P594, L6832, P273, and L5767, P680; and match 3 ties from L.C.R.C. L6586, P204. Field measurements were observed between the following corners:

| H-3 to I-3 | Meas. | I-2 to I-3 | Meas. | J-3 to I-3 | Meas. | I-3 to I-4 | meas. |
|------------|--------|------------|-----------|------------|-----------|------------|-----------|
| 2693.89 | | 2681.69 | | 2728.40 | | 2665.88' | |
| 2656.50 | G.L.O. | 2640.00 | G.L.O. | 2689.50 | G.L.O. | 2640.00 | G.L.O. |
| | | 2681.81 | Tax Desc. | 2728.69 | Tax Desc. | 2665.87 | Tax Desc. |

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I replaced the existing 1/2" iron in asphalt pavement with a 3/4" X 24" iron rod with a 2" aluminum cap stamped "Macomb County Monument MI Act 345 #37281" in a new monument box. Witnesses are as follows:

| | | |
|----------|---------|---|
| AZ. 30° | 78.53' | Set mag. nail and Macomb County Remon. tag W. face 16" Spruce |
| AZ. 68° | 38.36' | Set mag. nail and Macomb County Remon. tag S. face 12" Spruce |
| AZ. 90° | 77.06' | Set mag. nail and Macomb County Remon. tag S. face 12" Ash |
| AZ. 142° | 97.28' | Set mag. nail and Macomb County Remon. Tag W. face 14" Ash |
| AZ. 263° | 107.30' | Set mag. nail and Macomb County Remon. Tag N. face 22" Poplar |
| AZ. 266° | 166.99' | Set mag. nail and Macomb County Remon. Tag N. face u-pole |

ACCEPTED BY THE MACOMB COUNTY SURVEY PER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 10/13/98

 WILLIAM E. SCDERBERG, P.S., CHAIRMAN

The selected location is accepted by me and generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by John N. Redash Date 12-23-98
 Surveyor's Michigan License No. 37281