

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

B997903

For corners in

<u>MACOMB</u> (County)	Located In:	Corner Code -#
	MACOMB TWP.	
1. Public Land Survey	T <u>3N</u> R <u>13E</u>	<u>J-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

LIBER **06161 PG 253**

Register of Deeds Stamp & File Number

I, BRUCE ANTCLIFF, in a field survey on NOVEMBER 23, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|--|--|
| GLO-Post, NO WITS. REMAIN | MDOT (1989)-PK IN 3/4" PIPE
N&T IN PP, N50W, 8.43'
TOP CENTER HYDRANT, N30E, 7.00'
N&T IN 10" PINE, N85E, 53.01'
PK IN NORTH EDGE PAVT, S05W, 35.54' |
| MDOT (1961)-3/4" PIPE
32" ELM, N03W, 16.39'
13" ELM, N70W, 43.81'
18" ELM, N82E, 82.40'
N EDGE PAVT, SOUTH, 40.40' | LCRC (1989) L4685,P294-PK IN 3/4" PIPE
TOP CENTER HYDRANT, N30E, 7.00'
NAIL IN 10" PINE, N85E, 53.01'
PK IN NORTH OF BIT., S05W, 35.54'
N&T IN PP, N50W, 8.43' |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- FOUND 3/4" PIPE
- FOUND AND VERIFIED THREE OF THE ABOVE WITNESSES

93 DEC 22 AM 9:05

CARMELA SABAUGH
REGISTER OF DEEDS
MACOMB COUNTY, MI

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-1-93

Frank J. DeDecker
FRANK J. DEDecker, P.S., PE, CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET MACOMB COUNTY REMONUMENTATION MARKER AND CAP #25826
- WITNESSES
- FND MDOT N&T SW FACE PP, N60W, 8.35'
- TOP CENTER HYDRANT, N30E, 6.90'
- S. EDGE LIGHT POST FOR #22381, N55E, 23.37'
- FND MDOT N&T N FACE 14" PINE, N85E, 52.96'



The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by Bruce Antcliff Date 12-9-93

Surveyor's Michigan License No. 25826