

APR 07 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Macomb _____
(County)

Located In: Macomb Twp. Corner Code #

- | | | | |
|------------------------------------|---------|---------|---------|
| 1. Public Land Survey | T-3-N | R-13-E | L-1 |
| | T-_____ | R-_____ | _____ |
| | T-_____ | R-_____ | _____ |
| | T-_____ | R-_____ | _____ |
| 2. Property Controlling in Section | S-_____ | T-_____ | R-_____ |
| | S-_____ | T-_____ | R-_____ |
| 3. Miscellaneous Property in Sec. | S-_____ | T-_____ | R-_____ |
| | S-_____ | T-_____ | R-_____ |

SECTION

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 11-18-97
William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, John N. Redash, in a field survey on October 17, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

1817	Not set	G.L.O. Notes	W. Preston	N/A	N/A
1983	1/2" Pipe	L.C.R.C.	R. Smith	#16052	L3573, P519
1983	1/2" Pipe	Survey	R. Smith	#16052	L3578, P33
1994	Mon. box	Survey	G. James	#19835	L6423, P777
1995	1/2" Pipe in mon. box	Survey	M. Feindt	#3920	L6877, P476
1997	1/2" Pipe in mon. box	Survey	D. King	#30085	Unrecorded Survey

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A 1/2" iron pipe in monument box in asphalt pavement 0.5' ± north of existing centerline currently occupies this corner. The following witness ties were used to recover and verify its position; 4 witness ties match current measurements from L.C.R.C. L 3573, P519, Survey L3578, P33, and Survey L6877, P476. L1 is common to corner L13.

Field observations were obtained between the following corners:

K-1 to L-1	2708.88 meas.	No. G.L.O.	2709.01 Rec. Unrecorded Survey (D. King #30085)
L-1 to M-1	2696.63 meas.	No. G.L.O.	



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I replaced the existing 1/2" iron pipe with a 3/4" X 24" iron rod with a 2" aluminum cap stamped "Macomb County Monument MI Act 345 #37281" in the existing monument box. Witness ties are as follows:

- N. 70° W., 101.20' P.K. Nail and Macomb County Remon. washer south face U-pole
- N. 18° E., 28.14' P.K. Nail and Macomb County Remon. washer southeast face U-pole
- N. 85° E., 140.03' P.K. Nail and Macomb County Remon. washer southeast face U-pole
- S. 73° E., 156.65' P.K. Nail and Macomb County Remon. washer east face U-pole
- S. 10° W., 31.90' P.K. Nail and Macomb County Remon. washer east face U-pole

The selected location is accepted by me and generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by John N. Redash Date December 17, 1997
Surveyor's Michigan License No. 37281