


LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Macomb Located In: Macomb Twp. Corner Code #
 (County)

- 1. Public Land Survey T-3-N R-13-E L-3
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling in Section S _____ T _____ R _____
 S _____ T _____ R _____
- 3. Miscellaneous Property in Sec. S _____ T _____ R _____
 S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____



SURVEY &
 REMONUMENTATION

MAR 15 1999

SECTION

Register of Deeds Stamp & File Number

I, John N. Redash, in a field survey on Jan. 6, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

1817	Set post	G.L.O. Notes	W. Preston	N/A	N/A
1979	Found 1/2" rerod	L.C.R.C.	J. Fenn	#23505	L3168, P267
1979	N/A	Survey	J. Fenn	#23505	L3148, P837
1979	Found 1/2" rerod	L.C.R.C.	W. Soderberg	#17635	L3179, P738
1979	Found 1/2" rerod	Survey	W. Soderberg	#17635	L3179, P742
1989	Found 1/2" iron rod	L.C.R.C.	M. Dunn	#30081	L4687, P333

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A found 1/2" iron rod in a wooded area 0.3' south of a 3" steel post currently occupies this corner. The following witness ties were used to recover and verify its position: One tie matches current measurements from L.C.R.C.s L3168, P267, L3179, P738, and L.C.R.C. L4687, P333. Field measurements were observed between the following corners:

K-3 to L-3		L-3 to M-3	
2681.72	Meas.	2685.11	Meas.
2656.50	Rec. G.L.O.	2656.50	Rec. G.L.O.
		2683.42	Rec. L.C.R.C.
			Rec. Survey
			L3168, P267 and L3179, P738
			L3148, P837 and L3179, P742

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I replaced the found 1-1/2" rerod with a 4" X 36" concrete monument with a 2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #37281" in a wooded area. Witness ties are as follows:

- AZ. 06° 12.45' Found P.K. nail in W. face 16" Ash
- AZ. 110° 12.56' Found P.K. nail in N.E. face 6" Oak
- AZ. 265° 7.58' Found P.K. nail in S. face 16" Maple
- AZ. 320° 15.46' Found P.K. nail in S. W. face 16" Maple Cluster

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 10/13/98

 WILLIAM E. SODERBERG, P.S., CHAIRMAN

The selected location is accepted by me and generally accepted by Professional Surveyors as the best available evidence of the position of the original corner

Signed by John N. Redash
 Surveyor's Michigan License No. 37281

Date 12-23-98

830