

APR 29 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Macomb Located In: Macomb Twp. Corner Code #
(County)

- 1. Public Land Survey T 3N R 13E L-9
 T _____ R _____
 T _____ R _____
 T _____ R _____
 - 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
 - 3. Miscellaneous S _____ T _____ R _____
 Property in Section S _____ T _____ R _____
4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert D. Kohn, in a field survey on July 6, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1817 10" Ash	G.L.O.	W. Preston	n/a	Notes
1995 F.I.B. set cap	Survey	G. James	#19835	L6575 P47

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A 1/2" iron bar with cap #19835 at the base of 48" stump currently occupies this corner. A prominent tree lie extends to the north from this position. The following witness ties were used to verify and recover its position:
2 ties match Survey L6575 P47

Field measurements were made between the following corners:

K-9 to L-9	2696.84	meas.	
	2663.10	rec.	G.L.O.
L-9 to M-9	2692.84	meas.	
	2663.10	rec.	G.L.O.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 8-15-95
William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I replaced the capped re-bar with a 3/4" x 24" iron rod with a 2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #26459".

Due N.	67.67'	P.K. nail and M.C.R. tag in W. face 8" Poplar
S.80° E.	22.64'	P.K. nail and M.C.R. tag in N. face 12" Poplar
S.10° E.	24.58'	P.K. nail and M.C.R. tag in N. face 4" Tree
Due W.	84.80'	P.K. nail and M.C.R. tag in S. face 36" Walnut

The selected location is accepted by me and generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by Robert D. Kohn

Date Dec 11, 1995

Surveyor's Michigan License No. 26459

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

