

APR 29 1996
COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Macomb (County) Located in: Macomb Twp Corner Code #

- 1. Public Land Survey T 3N R 13E L-11
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Section S _____ T _____ R _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert D. Kohn, in a field survey on July 6, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1817	3" Iron wood box	G.L.O.	W. Preston	n/a	Notes
1979	5/8" Pipe	L.C.R.C.	W. Soderberg	#17635	L3059 P204
1979	5/8" Pipe	L.C.R.C.	W. Soderberg	#17635	L3089 P947
1980	5/8" Pipe	L.C.R.C.	W. Soderberg	#17635	L3258 P716
1980	5/8" Pipe	Survey	W. Soderberg	#17635	L3293 P828
1987	1/2" Pipe	Survey	D. King	#30085	L4306 P713
1992	5/8" Pipe	L.C.R.C.	W. Soderberg	#17635	L5578 P695

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A 3/4" iron pipe in asphalt pavement currently occupies this corner. The following witness ties were used to verify and recover its position:
4 ties match L.C.R.C. L3059 P204; L3089 P947
4 ties match Survey L3258 P716
4 ties match L.C.R.C. L5578 P695

Field measurements were made between the following corners:

K-11 to L-11	2685.06	meas.	G.L.O.	2653.2
	2684.97	rec.	plat	L93 P33
L-11 to M-11	2691.12	meas.		
	2653.20	rec.	G.L.O.	
	2630.97	rec.	Survey	L3293 P828

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I replaced the 3/4" iron pipe with a 3/4" x 24" iron rod with a 2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #26459" with a new monument box.

- N.60° E. 61.27' P.K. nail and M.C.R. tag in S. face utility pole
- S.60° E. 63.88' P.K. nail and M.C.R. tag in N.E. face utility pole
- Due S. 37.01' P.K. nail and M.C.R. tag in W. face 24" Maple
- S.70° W. 75.86' P.K. nail and M.C.R. tag in N.W. face utility pole

The selected location is accepted by me and generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by Robert D. Kohn Date Dec 11, 1995

Surveyor's Michigan License No. 26459

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983



ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 8-18-95
William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN