

LIBER 06166P059

B999672

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MACOMB

(County)

Located In: Macomb Township Corner Code #/

RECORDED IN MACOMB COUNTY RECORDS AT: 8:30 A M.

DEC 28 1993

Signature of Clerk - REGISTER OF DEEDS MACOMB COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

- 1. Public Land Survey T 3N R 13E M-9
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No.
5. Private Claims

Grid table with columns A-M and rows 2-13 containing numbers 1-36.

I, Shelby W. Money, in a field survey on November 18, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

LCRC (1977) L 2862 P.854 CHESTERFIELD TOWNSHIP / CONTROLLING SECTION 30, T.3N., R.14E. STONEROCK #13601 CORNER CODE #A-9
LCRC (1990) CHESTERFIELD TOWNSHIP / CONTROLLING SECTION 19, T.3N., R.14E. STEVEN DUNN #28403 CORNER CODE #A-9
LCRC (1991) CHESTERFIELD TOWNSHIP / CONTROLLING SECTION 19, T.3N., R.14E. DeDECKER #6386 CORNER CODE #A-9

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND RAILROAD SPIKE
THIS CORNER VERIFIED BY:
FOUND ALL RECORDED WITNESSES
HUEGEL FARM ACRES SUBDIVISION MACOMB TOWNSHIP UNRECORDED

FOUND 1/2" REBAR BELOW RAILROAD SPIKE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REMOVED RAILROAD SPIKE AND PK NAIL AND REPLACED WITH 3/4" BAR WITH MACOMB COUNTY REMONUMENTATION MARKER #30092 IN A MONUMENT BOX
WITNESSES:
Az 06° 44.53' FOUND A PK IN THE WEST FACE OF A UTILITY POLE
Az 57° 73.35' FOUND A PK WITH "SDA" TAG IN THE NORTHWEST FACE OF A 24" TREE
Az 109° 96.10' FOUND A PK IN THE SOUTHWEST FACE OF A UTILITY POLE
Az 227° 106.10' FOUND THE NORTHWEST CORNER OF HOUSE #24980

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by Shelby W. Money Date 12/4/93
Surveyor's Michigan License No. 30092

Professional Surveyor Seal for Shelby W. Money, No. 30092, Michigan. Includes text: 'ACCEPTED BY THE MACOMB COUNTY SURVEYOR PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 AT A MEETING HELD ON 12-15-93' and 'FRANK J. DeDECKER, P.S., PE, CHAIRMAN'.