

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

RECORDED IN MACOMB COUNTY
RECORDS AT: 8:30A M.

DEC 28 1993

Carmella [Signature]
CLERK - REGISTER OF DEEDS
MACOMB COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

Table with columns: MACOMB (County), Located In: Macomb Township, Corner Code: M-11. Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13, containing numerical values for survey points.

I, Shelby W. Money, in a field survey on November 18, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

MACOMB COUNTY ROAD COMMISSION (1959) UNRECORDED CORNER CODE A-11
LCRC (1987) CHESTERFIELD TOWNSHIP / CONTROLLING IN SECTION 31, T.3N., R.14E.
LCRC (1979) MACOMB TOWNSHIP / CONTROLLING IN SECTION 36, T.3N., R.13E.
LCRC (1988) CHESTERFIELD TOWNSHIP / CONTROLLING IN SECTION 31, T.3N., R.14E.
LCRC (1979) MACOMB TOWNSHIP / CONTROLLING IN SECTION 36, T.3N., R.13E.
LCRC (1979) MACOMB TOWNSHIP / CONTROLLING IN SECTION 36, T.3N., R.13E.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND MONUMENT BOX AT CENTERLINE IRON WITH CAP #17622

THIS CORNER VERIFIED BY: HOOPER SUBDIVISION SECTION 31 CHESTERFIELD TOWNSHIP
ERB INDUSTRIAL PARK SUBDIVISION SECTION 36 MACOMB TOWNSHIP
FENCE LINES RUNNING NORTH AND SOUTH

LIBER 29
LIBER 77

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REMOVED IRON WITH CAP #17622 AND REPLACED WITH 3/4" BAR AND MACOMB COUNTY REMONUMENTATION MARKER AND CAP #30092 WITHIN EXISTING MONUMENT BOX

WITNESSES: NORTH 59.45' FOUND PK NAIL W/MCRC TAG IN THE WEST FACE OF A 24" TREE
N 60° E 80.65' FOUND PK W/MCRC TAG
N 25° W 33.60' FOUND CHISELED "X" IN THE EAST EDGE OF A SANITARY MANHOLE
S 70° E 97.10' SET PK NAIL W/MCW TAG IN THE NORTH FACE OF AN 18" ELM TREE
S 20° E 93.12' FOUND NORTHWEST CORNER OF CEMENT BLOCK AT HOUSE #25032
SOUTH 60.06' FOUND CONCRETE MONUMENT WITH CAP #15403

ACCEPTED BY THE MACOMB COUNTY SURVEY PEBER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-15-93
FRANK J. DEDCKER, P.S., PE, CHAIRMAN

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by Shelby W. Money Date 12-15-93
Surveyor's Michigan License No. 30092

