

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MACOMB (County)

Located In: Macomb Township Corner Code # M-12

RECORDED IN MACOMB COUNTY RECORDS AT: 8:30 A.M.

DEC 28 1993

Register of Deeds Stamp & File Number

- 1. Public Land Survey T 3N R 13E M-12
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

- 4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. Cell 12,36 contains a black dot.

I, Shelby W. Money, in a field survey on November 18, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: GLO POST, NO WITNESSES REMAIN

LCRC (1987) L.4366 P.690 KOBS #14097
CHESTERFIELD TOWNSHIP / CONTROLLING SECTION 31, T.3N., R.14E. CORNER CODE #A-12
FOUND BOAT SPIKE
NORTH/NORTHWEST 18.23' PK NAIL IN 16" OAK TREE
NORTHWEST 33.42' PK NAIL IN 12" OAK TREE
WEST/SOUTHWEST 16.69' PK NAIL IN 32" OAK TREE
SOUTH/SOUTHWEST 5.76' PK NAIL IN 12" OAK TREE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND BOAT SPIKE
THIS CORNER VERIFIED BY:
FOUND MOST OF THE ABOVE WITNESSES
TREE LINE RUNNING EAST

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-15-93
FRANK J. DeDECKER, PS, PE, CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REMOVE BOAT SPIKE AND SET 3/4" BAR WITH A MACOMB COUNTY REMONUMENTATION MARKER #30092
WITNESSES:
N 60° W 18.12' FOUND PK NAIL W/RAY DONNELLY TAG IN THE NORTHEAST FACE OF A 16" OAK TREE
N 40° W 33.73' SET PK NAIL W/MACOMB COUNTY REMONUMENTATION TAG IN THE NORTHEAST FACE OF A 14" OAK TREE
S 15° W 5.56' FOUND PK NAIL W/RAY DONNELLY TAG IN THE NORTH FACE OF A 14" OAK TREE
S 85° W 16.61' SET PK NAIL W/MACOMB COUNTY REMONUMENTATION TAG IN THE NORTH FACE OF A 32" OAK TREE
NORTH 51.75' CORNER "<" ANGLE POST IN CONCRETE
NORTH 44.00'± FOUND IRON W/CAP #16052

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by [Signature] Date 12-15-93
Surveyor's Michigan License No. 30092

