

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &
 REMONUMENTATION

For corners in

APR 07 1998

MACOMB COUNTY
 (County)

Located In: MACOMB TOWNSHIP Corner Code # E-6

1. Public Land Survey T 3 N R 13 E
T R
T R
T R

2. Property Controlling in Section S T R Sec-2
S T R
S T R

3. Miscellaneous Property in Sec. S T R
S T R

SECTION

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1890 AT A MEETING HELD ON 9-22-97
William E. Soderberg
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, ROBERT H. BIRKETT, in a field survey on FEBRUARY 12, 1997 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- E-6
- LCRC LIBER 2332 PAGE 295 HERBERT J. KOBBS, P.S. #14097 FOUND 5/8" IRON AT INTERSECTION OF FENCES.
 - LCRC LIBER 4602 PAGE 725 ROGER J. STECKER, P.S. #30103 FOUND 5/8" IRON.
 - LCRC LIBER 6281 PAGE 175 SHELBY W. MONEY, P.S. #30092 FOUND 5/8" IRON.
 - LCRC LIBER 6523 PAGE 921 ROBERT D. KOHN, P.S. #26459 FOUND 5/8" IRON AND REPLACED WITH 3/4" X 24" IRON WITH ALUMINUM REMON CAP #26459.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-6 FOUND 3/4" IRON ROD WITH MACOMB COUNTY REMON CAP #26459 FROM LCRC LISTED AS ITEMS 2 AND 3 IN SECTION A, FOUND WITNESS AS LISTED IN SECTION A, WITNESSES LISTED IN LCRC ITEM 4, IN SECTION A, DID NOT MATCH REMONUMENTED POSITION.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-6
 REPLACED 3/4" IRON ROD WITH MACOMB COUNTY REMON CAP #26459, WITH A CONCRETE MONUMENT FOR PINWOOD VILLA'S WEST SUBDIVISION. RESET REMON CAP #26459 ON MONUMENT.

- AZ. 30° 14.92 FEET TO MACOMB COUNTY REMON WASHER FOUND IN EAST FACE OF MULTIPLE CHERRY.
- AZ. 90° 15.80 FEET TO MACOMB COUNTY REMON WASHER FOUND IN NORTH FACE OF TWIN 18" CHERRY.
- AZ. 170° 4.66 FEET TO MACOMB COUNTY REMON WASHER FOUND IN NORTHEAST FACE OF 16" BOX ELDER.
- AZ. 270° 24.44 FEET TO MACOMB COUNTY REMON WASHER FOUND IN NORTH FACE OF 6" ASH.

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Robert H. Birkett Date 11/10/97
 Surveyor's Michigan License No. 41094

717