

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>MACOMB</u> (County)	Located in: Macomb Township	Corner Code # B-13
1. Public Land Survey	T <u>3N</u> R <u>13E</u>	
	T _____ R _____	
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	<i>Seg. # 2 pm</i>
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Randy Kolehouse, in a field survey on November 20 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

B-13	1817	G.L.O. Notes	Preston	N/A	Post
	1978	L.C.R.C. L. 2940 P. 349	Patterson	#17631	P.K. Nail
	1979	L.C.R.C. L. 3184 P. 576	Fenn	#23505	P.K. Nail
	1988	L.C.R.C. L. 4790 P. 790	Soderberg	#17635	P.K. Nail
	1988	MDOT Notes	N/A	N/A	P.K. Nail
	1993	L.C.R.C. L. 6166 P. 013	Antcliff	#25826	5/8" Rebar w/Remon. Cap

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-13 ~~Previous remonumentation iron and cap has been destroyed during M-59 reconstruction. Reset a 3/4" rebar in an existing monument box using two remaining witnesses per L.C.R.C. L. 6166 P. 013 (1994). Also check recorded distances to A-13 and C-13.~~

L.C.R.C. L. 6166 P. 013 (1993)  
 MDOT N & T NW Face P. Pole S 51° W 78.68'  
 Nail & MC Tag NE Face P. Pole S 27° E 59.90'

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-13-94  
*William E. Soderberg*  
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

Measures East to C-13 = 2664.26' (MDOT = 2664.19') (AEW 1992 = 2664.21')  
 Measures East to B-1 = 592.21' (AEW 1992 = 592.21')  
 Measures West to A-13 (A-1) = 2086.48' (Fenn 1979 = 2086.41') (Soderberg 1988 = 2086.54') (MDOT 1988 = 2086.49') (AEW 1992 = 2086.47')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-13 I set a 3/4" x 24" iron rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #25854" in an existing monument box.

"+" SW Rim MBT M.H. N 40° E 64.69'  
 PK & Macomb Co. Remon. Tag NE Face Util. Pole S 27° E 59.90'  
 PK & Macomb Co. Remon. Tag W Face Util. Pole S 10° W 61.42'  
 Nail w/MDOT Tag NW Face Util. Pole S 51° W 78.68'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Randy J. Kolehouse Date 12/16/94  
 Surveyor's Michigan License No. 25854

