

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &
 REMONUMENTATION

For corners in

MACOMB Located In: Corner Code #
 (County) MACOMB TOWNSHIP

1. Public Land Survey T 3 N R 13 E A-12
 T ___ R ___
 T ___ R ___
 T ___ R ___

2. Property Controlling S ___ T ___ R ___
 in Section S ___ T ___ R ___
 3. Miscellaneous S ___ T ___ R ___
 Property in Sec. S ___ T ___ R ___

APR 07 1998

SECTION
 ACCEPTED BY THE MACOMB COUNTY SURVEY PEER
 GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN
 PUBLIC ACT 345 OF 1990 AT A MEETING HELD
 ON 8-5-73
William E. Soderberg
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, ROBERT H. BIRKETT, in a field survey on SEPTEMBER 9, 1997 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 1974, N.C. JONES, FOUND 1/2" IRON ROD, L. 2500, P. 789.
 1978, R. PATTERSON #17631, FOUND IRON IN MONUMENT BOX, L. 2940, P. 349.
 1978, W. SODDERBURG # 17635, FOUND 1/2" RE-ROD IN MONUMENT BOX, L. 3059, P. 205.
 1979, J. FENN, FOUND 1/2" RE-ROD IN MONUMENT BOX, L.C.R.C., L. 3184, P. 575.
 1993, D. PAWLACZYK #17632, SET MACOMB COUNTY MONUMENT IN MONUMENT BOX, L.C.R.C. L. 6166, P. 79.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 FOUND REMON IRON AND CAP IN MONUMENT BOX, CENTER OF ASPHALT ROAD (HAYES) AT DRAIN CROSSING. ORIGINAL REMON MONUMENT WAS DISTURBED DURING CONSTRUCTION OF BOX CULVERT AT DRAIN CROSSING.

- L. 3184, P. 575
 S. 45° E. 187.79' NORTHWEST CORNER BRICK RANCH HOUSE.
 NORTH 61.66' EAST 1/4 CORNER SECTION 36 SHELBY TOWNSHIP.
 S. 20° W. 82.79' NORTH RIM STORM MANHOLE.

DISTANCES (NONE SHOWN ON L. 6166, P. 79)
 A-12 TO A-11 2737.01' GROUND
 A-12 TO A-13 2615.29' GROUND



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 RESET 3/4" X 24" IRON WITH A 2" DIAMETER ALUMINUM CAP STAMPED "MACOMB COUNTY MONUMENT MI ACT 345 A-12 41094" IN EXISTING MONUMENT BOX.

- AZ. 0° - 61.68' - FOUND MACOMB COUNTY MONUMENT IN MONUMENT BOX, M-12 SECTION 36 SHELBY TOWNSHIP.
 AZ. 20° - 142.75' SET MACOMB COUNTY WITNESS TAG IN NORTHWEST FACE UTILITY POLE.
 AZ. 135° - 187.75' TO NORTHWEST CORNER BRICK HOUSE #15215 WINTER PARK DRIVE.
 AZ. 200° - 83.31' TO CHISLED "+" ON NORTH RIM STORM MANHOLE.
 AZ. 285° - 80.53' TO CENTER OF HYDRANT.

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Robert H. Birkett Date 12/15/97
 Surveyor's Michigan License No. 41094

716