

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in COMMISSION

CHESTERFIELD Located In: CHESTERFIELD TOWNSHIP Corner Code #  
 (County) CHESTERFIELD TOWNSHIP

1. Public Land Survey T 3N R 14E A-4  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, CRAIG P. AMEY, in a field survey on AUGUST 25, 19 94 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		6		5		4		3		2		1
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO 1817 Pages 55-57 William Preston No witnesses found  
 LCRC 1976 L 2687 P 612 Robert L. Smith, #16052 Found 1" iron  
 LCRC 1987 L 4306 P 691 Herbert J. Kobs, #14097 Found 1" iron bar  
 Corner is common to M-4 T3N, R13E

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found, 1" iron at intersection of north, south and west fence lines in a field approximately 1320' east of fairchild rd.  
 This corner verified by: Found and matched existing witnesses

LCRC L 4306 P 691  
 N 23.65' Found form nail in 10" oak  
 ENE 2.35' Found form nail in a 6" oak  
 E 28.43' Found form nail in a 12" oak  
 S 16.07' Found form nail in a 42" oak

S 2669.24' To the southeast corner of section 7  
 N 2665.21' To the northwest corner of section 7

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 9-27-94

*William E. Soderberg*  
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced 1/2" pipe with a 3/4" x 24" iron and a macomb county remonumentation cap stamped:  
 "MACOMB COUNTY MONUMENT"  
 "34970"  
 "MI ACT 345"

73° 2.35' Form nail in the south face of a 6" oak  
 97° 28.43' Form nail in the south face of a 12" oak  
 178° 17.30' Form nail in the west face of a 42" oak  
 330° 23.65' Form nail in the east face of a 10" oak

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.



Signed by Craig P. Amey  
 Surveyor's Michigan License No. 34970

Date 12-15-94