

SURVEY & REMONUMENTATION

APR 28 1995

C0158340 LIBER:06543 PAGE:362 08:35A 01/05/1995
CARMELLA SABAUGH-MACOMB COUNTY, MI REG/DEEDS

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>MACOMB</u> (County)	Located In: CHESTERFIELD TOWNSHIP	Corner Code # _____
1. Public Land Survey	T <u>3N</u> R <u>14E</u>	<u>A-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, _____, in a field survey on _____, 19____ do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O.	(1817)	WILLIAM PRESTON	NO WITNESSES REMAIN
LCRC	(1990)	LIBER 4990 PAGE 166 STEVEN E. DUNN #28408	FOUND 1/2" I. ROD
LCRC	(1990)	LIBER 5024 PAGE 937 FRANK J. DeDECKER #8386	FOUND 1/2" IRON ROD
SURVEY	(1990)	UNRECORDED STEVEN E. DUNN #28408	FOUND 1/2" I. ROD

CORNER IS COMMON TO A-8, T.3N., R.14E., MACOMB COUNTY

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON THIS CORNER VERIFIED BY: FOUND AND MATCHED ALL EXISTING RECORDED WITNESSES.

LCRC L 4990 P 166
ESE 25.12' NORTHWEST CORNER OF FOUNDATION OF ADDITION TO NORTH
SW 20.97' NORTHWEST CORNER OF FOUNDATION OF WEST END EXISTING HOUSE
W 25.28' SET PK'NAIL IN THE NORTH SIDE OF A 12" MAPLE

LCRC L 5024 P 937
2° 68.33' PK'NAIL W/SDA TAG IN THE EAST FACE OF A UTILITY POLE
108° 25.13' CORNER OF HOUSE #49939 (BLOCK)
215° 20.95' CORNER OF HOUSE #49939 (BLOCK)
273° 25.29' PK'NAIL W/SDA TAG IN THE NORTH FACE OF A 12" MAPLE

ACCEPTED BY THE MACOMB COUNTY SURVEY PEE GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 9-27-94
William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN

N 2678.50' NORTHWEST CORNER OF SECTION 24 (M-7)
S 2671.66' SOUTHWEST CORNER OF SECTION 24 (M-9)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
REPLACED 1/2" IRON WITH A 3/4" x 24" IRON AND A MACOMB COUNTY REMONUMENTATION CAP STAMPED: "MACOMB COUNTY MONUMENT", "34970", "MI ACT 345"

2° 68.33' FOUND A PK'NAIL W/SDA TAG IN THE EAST FACE OF A UTILITY POLE
273° 25.29' FOUND A PK NAIL W/SDA TAG IN THE NORTH FACE OF A 12" MAPLE
108° 23.13' FOUND CORNER OF A HOUSE #49939
215° 20.95' FOUND CORNER OF A HOUSE #49939

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.



Signed by *Craig P. Amey*
Surveyor's Michigan License No. _____

Date 12-15-94