

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MACOMB
(County)

Located In: Chesterfield Township
Corner Code # A-9

RECORDED IN MACOMB COUNTY
RECORDS AT: 8:30 A.M.

DEC 28 1993

Carmella A. ...
CLERK - REGISTER OF DEEDS
MACOMB COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

- 1. Public Land Survey
2. Property Controlling in Section
3. Miscellaneous Property in Sec.
4. Lot No.
5. Private Claims

Grid table with columns A-M and rows 2-13, containing numbers 1-36.

I, Shelby W. Money, in a field survey on November 18, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO POST, NO WITNESSES REMAIN
LCRC (1977) L. 2862 P. 854 STONEROCK #13601 CORNER CODE #A-9
LCRC (1990) L. 4990 P. 164 CHESTERFIELD TOWNSHIP / CONTROLLING SECTION 19, T.3N., R. 14E. STEVEN DUAN #28408 CORNER CODE #A-9
LCRC (1991) L. 5024 P. 934 CHESTERFIELD TOWNSHIP / CONTROLLING SECTION 19, T.3N., R. 14E. DeDECKER #8386 CORNER CODE #A-9

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND RAILROAD SPIKE
THIS CORNER VERIFIED BY:
FOUND ALL RECORDED WITNESSES
HUEGEL FARM ACRES SUBDIVISION MACOMB TOWNSHIP UNRECORDED
FOUND 1/2" REBAR BELOW RAILROAD SPIKE

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-15-93
FRANK J. DeDECKER, PS, PE, CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REMOVED RAILROAD SPIKE AND PK NAIL AND REPLACED WITH 3/4" BAR WITH MACOMB COUNTY REMONUMENTATION MARKER #30092 IN A MONUMENT BOX
WITNESSES:
Az 06° 44.53' FOUND A PK IN THE WEST FACE OF A UTILITY POLE
Az 57° 73.35' FOUND A PK WITH "SDA" TAG IN THE NORTHWEST FACE OF A 24" TREE
Az 109° 96.10' FOUND A PK IN THE SOUTHWEST FACE OF A UTILITY POLE
Az 227° 106.10' FOUND THE NORTHWEST CORNER OF HOUSE #24980



The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by Shelby W. Money Date 12/14/93
Surveyor's Michigan License No. 30092